RESOLUTION AUTHORIZING CONTRACT MODIFICATION #02 FOR THE PURAC PHASE III PROJECT

MOTIONED BY: Velazquez SECONDED BY: Friedrich

WHEREAS, the North Hudson Sewerage Authority (hereinafter "Authority") is a public body, duly formed under the Sewerage Authorities law, constituting Chapter 138 of the Laws of New Jersey of 1946, as amended (Chapter 14A of Title 40 of the New Jersey Statutes Annotated) and possesses the powers set forth therein; and

WHEREAS, pursuant to the approval granted by virtue of R.18-061, the Authority has contracted with Rapid Pump & Meter Service Co., Paterson, N.J. in the amount of \$11,862,950.00 for the Purac Phase III Project; and

WHEREAS, one previous contract modification was approved in the amount of \$31,191.05, increasing the total contract price to \$11,894,414.05; and

WHEREAS, this contract modification has been requested in order to efficiently advance the project as described in the report identified as "Exhibit A", with the additional work being documented as required by JACOBS, the project engineer; and

WHEREAS, the Facilities Review Board has reviewed the proposal and recommends the approval of the requested contract modification.


NOW, THEREFORE, BE IT RESOLVED that the Authority hereby authorizes the execution and implementation of said contract modification # 02 with no increase in contract...

DATED: DECEMBER 17, 2020

RECORD OF COMMISSIONERS' VOTE

	YES	NO	ABSENT
Commissioner Soares			X
Commissioner Kappock	X		
Commissioner Marotta	X		
Commissioner Gardiner	X		
Commissioner Friedrich	X		
Commissioner Sanchez	X		
Commissioner Velazquez	X		
Commissioner Roque	X		
Commissioner White	X		

THIS IS TO CERTIFY THAT THIS RESOLUTION WAS DULY ADOPTED BY THE NORTH HUDSON BOARD OF COMMISSIONERS ON DECEMBER 17, 2020.





Water Business Group Jacobs New Jersey Office 412 Mt Kemble Avenue Morristown, NJ 07962 **O+1** 973 267 0555

November 19, 2020

William P. Machotka, P.E.
Section Chief
State of New Jersey Department of Environmental Protection
Municipal Finance and Construction Element
P.O. Box 425
Trenton, NJ 08625-0425

Subject: North Hudson Sewerage Authority

Project No. S340635-30

PURAC System Improvements Phase 3 - Physical System Improvements

Contract Modification No. P-02

Dear Mr. Machotka:

We have found it necessary to issue the following Contract Modification to the PURAC System Improvements Phase 3 – Physical System Improvements Project:

No. P-02:

- Lockable Switch Covers
- Addition of Silencers
- Skimmer Flight Modifications in Cells 3 and 4
- Filter Cell Level Transmitters
- Cells 3 and 4 New High-Side Impulse Lines
- Cell 5 Work Platform Modifications
- Replacement of Air Compressor Circuit Breakers
- Skimmer Flight Modifications in Cells 9 and 10
- (Credit) Elimination of Performance Test Lab Fees for all 10 cells
- (Credit) Elimination of 24-inch Waste Gate Manual Operator
- (Credit) Elimination of Blower Motor Thermostats
- (Credit) Elimination of Handrail
- (Credit) Unit Price Item U1 ALLOWANCE

Total Amount of the Modification No. P-02: \$0

Attached are two (2) copies of the completed NJDEP "Contract Modification Proposal and Acceptance Form", for the above-mentioned Contract Modification. The copies have been signed by the North Hudson Sewerage Authority (the Owner), Rapid Pump and Meter Service Co., Inc. (the Contractor) and signed and sealed by Jacobs (the Engineer). We would appreciate your review and approval of this modification.

Should you have any questions or require additional information, please call me at 862.242.7067

Sincerely,

CH2M HILL

Shivani Patel, P.E. Project Manager

Cc: Fredric J. Pocci, P.E., NHSA

Ernest Renda, Rencor

Steven Marsich, PE, Rapid Pump Steve Kulcsar, PE, Rapid Pump

Dejan Davidovic, Jacobs Michael Curley, NJDEP

NJO File

Ι.	1. ISSUING OFFICE 2. PROJECT NO.		3. CONTRACT NO.	4. MODIFICATION NO.			
North Hudson Sewerage Authority S340635-30		PURAC System Upgrades Phase 3-Services During Construction	Mod # P-02				
5.	TO (CONTRACTOR)		6. PROJECT LOCATION AND DESCRIPTION				
	285 Strai PO B	eter Service Co. Inc ght Street ox AY NJ 07509	Adams Street WWTP Hoboken, New Jersey				
7.	7. A proposal is required for making the hereinafter described change in accordance with specification and drawing revisions cited herein or listed in attachment hereto. Submit your proposal in space indicated on page 2, attach detailed breakdown of prime and sub-contract costs (See the clause of this contract entitled, "Changes". DO NOT start work under this proposed change until you receive a copy signed by the Contracting Officer of a directive to proceed).						
		Shivani Patel	, P.E./Project Manager				
	Date		, P.E./Project Manager Name and Title	Signature			

As a result	of the above, the contract price	ce is revised as follows:		
ITEM NO.	ITEM DESCRIPTION			TOTAL COST
1	Lockable Switch Covers			\$9,214.71
2	Addition of Silencers			\$32,083.33
3	Skimmer Flight Modificati	ons in Cells 3 and 4		\$22,536.42
4	Filter Cell Level Transmitt	ers		\$53,116.83
5	Cells 3 and 4 New High-Si	de Impulse Lines		\$1,804.81
6	Cell 5 Work Platform Mod	ifications		\$12,260.80
7	Replacement of Air Compr	ressor Circuit Breakers		\$9,684.26
8	Skimmer Flight Modificati	ons in Cells 9 and 10		\$9,800.00
9	9 Elimination of Performance Test Lab Fees for all 10 cells (C			(\$7,120.00)
Elimination of 24-inch Waste Gate Manual Operator (Credit)			(\$6,000.00)	
11	Elimination of Blower Mot	or Thermostats (Credit)		(\$1,114.00)
12	Elimination of Handrail (C	redit)		(\$6,000.00)
13	Unit Price Item U1 ALLOV	WANCE (Credit)		(\$130,267.16)
modification	mes will be discussed in a se	decreased or *remaining the separate time related change order for the		
	ng modification is hereby ac np & Meter Service Co, Inc.			Jacobs
CO	NTRACTOR	OWNER	(NJPE SEAL)	ENGINEER
BY:		BY:	BY:	
DATE: _	_	DATE:	DATE:	
APPROVA		W IEDSEV	DATE	
	STATE OF NE	W JERSE I	DATE	

9. ISSUING OFFICE	10. PROJECT NO.	11. CONTRACT NO.	12. MODIFICATION NO.
North Hudson Sewerage Authority	S340635-30	PURAC System Upgrades Phase 3 Services During Construction	Mod # # P-02
13. CONTRACTOR'S PR	OPOSAL – CHANGE IN O	CONTRACT PRICE	
	attach additional sheets as no		
(Proposed)			
See Attachment B			
December 41 is Change	O., da., N D. 02 fa., 4h a DUD	A.C. Caretana I In anadaa Dha	- 2 Coming During Constant
			se 3 Services During Construction ent of any and all claims against
			Owner from and waives all claims,
			g to the changed work including,
	for damages arising from de f contract, cardinal change		costs, home and field office overhead
•	<u> </u>		
NET INCREASE	NET DECREA	ASE	CALENDER DAYS INCREASE
\$ 0	\$ <u>0</u>		DAYS
DATE:	TYPE NAME AND TITI	LE: S	SIGNATURE:

14 ICCUING OFFICE & PROJECT NO	15 CONTRACT NO	16 MODIFICATION NO
14. ISSUING OFFICE & PROJECT NO.	15. CONTRACT NO.	16. MODIFICATION NO.
North Hudson Sewerage Authority, S340635	5-04 PURAC System Upgrades Phase 3 Services During Construction	Mod # P-02
17. ORIGINAL CONTRACT BID PRICE	11,862,950.00	
TOTAL OF PREVIOUS CHANGE ORD	ERS\$	31,191.05
TOTAL CONTRACT COST INCLUDIN	G CHANGE \$ 1	11,894,141.05
See Attachment C		
19. OTHER IMPACTS RESULTANT OF TH	IIS CHANGE:	
No other impacts on the Contractor at this order for these items and any COVID relat		sed in a separate time related change
20. RESUME OF NEGOTIATIONS OR REC	COMMENDATIONS (Loanee's Re	epresentative):
DATE: TYPE NAME AN REPRESENTATI		IGNATURE:

Attachment A

DESCRIPTION OF CHANGE

Issuing Office: North Hudson Sewerage Authority

Project Number: \$340952-30

Modification No: P-02

Box No. 8: DESCRIPTION OF CHANGE

1. Lockable Switch Covers

a. Furnish Model: Appleton FSK-1VS, NEMA 3R lockable switch covers at locations of Solenoid Valve local 120VAC disconnect switches

2. Addition of Silencers

a. Furnish and Install 2 Durr Universal Inlet Silencers Model Special RDY-12 (Inlet, CS EPA AIS) for the blowers

3. Skimmer Flight Modifications in Cells 3 and 4

- a. Modify the skimmer flight return wear blocks on Cells #3 and #4, as per RFI-035.
- b. Remove all FRP skimmer flights on Cells #3 and #4 and replace with new Marine-Grade Aluminum skimmer flights provided by AWC. Adjust flight wipers to conform to their respective beaches and the cell walls.
- c. Remove existing drive motor bases on Cells #3 and #4 and replace with new adjustable motor bases provided by AWC.
- d. Remove two "smooth" wheels from each side of all new aluminum flights. Replace with new "shouldered" wheels provided by AWC.
- e. Cut bearing support brackets and plug weld (2) anchor bolts for Cells 3 and 4. Install bumper guards along the top rails in Cells 3 and 4.
- f. Provide all delivery truck unloading services.
- g. Furnish any necessary miscellaneous hardware.

4. Filter Cell Level Transmitters

- a. Furnish and install Qty. 10: Endress+Hauser Micropilot FMR51 radar based level transmitters. One (1) for each DAF/Filter cell. Order one (1) transmitter with an expedited fabrication/ship schedule.
- Furnish and install Qty. 10: Endress+Hauser Bluetooth modules (BT10), Model No. 71377355. Factory install one (1) BT10 module in each radar-based level transmitter.
- c. Furnish and install Qty. 10: custom mounting brackets. Refer to attached Jacobs bracket design sketch and level transmitter dimensional drawings.
- d. Provide manufacturer's representative's field startup, testing, and training for the new level instruments. Estimate the startup of 10 level instruments with be concurrent with training of plant operations and maintenance staff. Estimate (2.5) 10-hour days.

- e. Provide shop drawing submittals for Engineer's review and approval, prior to purchase or manufacture.
- 5. Cells 3 and 4 High-Side Impulse Lines
 - a. Furnish and install new taps on the Emergency Bypass pipes for Filter Cells #3 and #4 to be used for connecting the "High-Side" impulse lines of the newly installed filter cell differential pressure transmitters. Install the new taps on the vertical pipe run, below the invert elevation of the upper horizontal pipe run.
 - b. Remove and relocate the newly installed High-Side impulse piping. Install new pipe and fittings as required to achieve impulse line alignment.
 - c. Install plug in abandoned tap.
- 6. Cell 5 Work Platform Modifications
 - a. Furnish and install access platform:
 - i. Steel platform with approximate dimensions of eighteen foot by nine-foot 18'x9').
 - ii. Install one (1) Fixed Ladder with Safety Cage.
 - iii. Install wall supports using epoxy anchors.
 - iv. Install galvanized grating
 - b. Furnish access platform in Cell #5:
 - i. New Grating Panels per updated platform layout RFI 049
 - ii. New Framing steel angles (4) x L3x3x3/8 per attached New Layout
 - iii. Ladder extension and mods per attached ladder modification detail
- 7. Replacement of Air Compressor Circuit Breakers
 - a. Replace the circuit breakers of four (4) air compressors.
- 8. Skimmer Flight Modifications in Cells 9 and 10
 - a. Remove (36) flights by removing the roller mounting bracket and chain link bracket.
 - b. Cut 1-1/2" off the gear motor side, of the flight for (36) flights.
 - c. Extend the cut notch accordingly in each flight.
 - d. Drill 4 x New Holes in each flight roller mounting bracket and chain-link bracket.
 - e. Freight and Handling. Dispatch all (36) x Flights to RPM's shop in Paterson, NJ. To expedite flight mods. As opposed to trimming and drilling on site.
 - f. Install and adjust (36) trimmed flights.
- 9. Elimination of Performance Test Lab Fees for all 10 cells (Credit)
 - a. Lab Tests not required during Performance Test
- 10. Elimination of 24-inch Waste Gate Manual Operator (Credit)
 - a. Removal of 24-inch Gate Manual Operator from Contract
- 11. Elimination of Blower Motor Thermostats (Credit)
 - a. Removal of Blower Motor Thermostats from Contract

- 12. Elimination of Handrail (Credit)
 - a. Removal of New Handrails Along Influent Channel from Project Scope
- 13. Unit Price Item U1 ALLOWANCE (Credit)
 - a. Credit of Allowance Item for Welded Steel Pipe and Appurts

Attachment B

CONTRACTOR'S PROPOSAL - CHANGE IN CONTRACT PRICE

Issuing Office: North Hudson Sewerage Authority

Project Number: \$340952-30

Modification No: P-02

Box No. 13: CONTRACTOR'S PROPOSAL - CHANGE IN CONTRACT PRICE

- 1. Lockable Switch Covers
 - a. Cost Proposal (RFQ-01) received from Rapid pump via email on June 15, 2020.
- 2. Addition of Silencers
 - a. Cost Proposal (RFQ-02) received from Rapid pump via email on October 21, 2020.
- 3. Skimmer Flight Modifications in Cells 3 and 4
 - a. Cost Proposal (RFQ-03) received from Rapid pump via email on September 24, 2020.
- 4. Filter Cell Level Transmitters
 - a. Cost Proposal (RFQ-04) received from Rapid pump via email on September 23, 2020.
- 5. Cells 3 and 4 High-Side Impulse Lines
 - a. Cost Proposal (RFQ-05) received from Rapid pump via email on October 13, 2020.
- 6. Cell 5 Work Platform Modifications
 - a. Cost Proposal (RFQ-06) received from Rapid pump via email on October 5, 2020.
- 7. Replacement of Air Compressor Circuit Breakers
 - a. Cost Proposal (RFQ-07) received from Rapid pump via email on September 23, 2020.
- 8. Skimmer Flight Modifications in Cells 9 and 10
 - a. Cost Proposal (RFQ-08) received from Rapid pump via email on October 26, 2020.
- 9. Elimination of Performance Test Lab Fees for all 10 cells (Credit)
 - a. Credit confirmed from invoice on December 10, 2019
- 10. Elimination of 24-inch Waste Gate Manual Operator (Credit)
 - a. Credit confirmed in transmittal from DeZurik on March 5, 2020

- 11. Elimination of Blower Motor Thermostats (Credit)
 - a. Credit confirmed in Submittal 11370-002-3 on July 8, 2020
- 12. Elimination of Handrail (Credit)
 - a. Credit confirmed in email from October 13, 2020
- 13. Unit Price Item U1 ALLOWANCE (Credit)
 - a. Reduction in Cost in Unit Price Item U1

Attachment C

NECESSITY FOR CHANGE AND REASON FOR OMISSION FROM PLANS AND SPECIFICATIONS

Issuing Office: North Hudson Sewerage Authority

Project Number: S340952-30

Modification No: P-02

Box No. 18: NECESSITY FOR CHANGE AND REASON FOR OMISSION FROM PLANS AND SPECIFICATIONS

- 1. Lockable Switch Covers The specified cover is not capable of being locked out/tagged out. The proposed switch covers will have this ability
- 2. Addition of Silencers Installation of the silencer is necessary to reduce noise from the blowers which was objectionable to the residents in the Shades Development behind the WWTP.
- 3. Skimmer Flight Modifications in Cells 3 and 4 The skimmer equipment supplier, AWC (who is under a separate supply contract with NHSA), was not satisfied with the performance of their FRP-based flight design and motor bases. AWC undertook a redesign effort and had new items fabricated at no charge to the Authority. It is necessary for the Phase 3 General Contractor to perform the field work associated with the skimmer modifications.
- 4. Filter Cell Level Transmitters The contract documents require the reuse of the existing level transmitters in the newly rehabilitated filter cells. However, the existing radar-based level transmitters don't work properly in the newly rehabilitated cells. A new level-instrument with a more concentrated "beam angle" was tested and proved to function appropriately, therefore new level transmitters are required for all cells to operate as required.
- 5. Cells 3 and 4 High-Side Impulse Lines The contract documents required installation of new impulse line taps in the same general location of the existing (demolished) pressure transmitter impulse line taps. Upon startup of the new filter cells, it was discovered that the location of the tap introduces air in the impulse line during the filter backwash, which causes the transmitter not to work properly. The taps for Cells 3 and 4 were relocated to an area of piping that will always be filled with water, even during a backwash.
- 6. Cell 5 Work Platform Modifications Per the Contract Documents the access platform was located in Cell 5, however, during construction it was agreed to move the platform to Cell 6. The resulting redesign required modifications of the platform grating and ladder to accommodate the existing vertical pipe in the area.

- 7. Replacement of Air Compressor Circuit Breakers Upon start-up of the air compressors there were issues with the air compressors tripping. Increasing the size of the circuit breaker has solved the issue.
- 8. Skimmer Flight Modifications in Cells 9 and 10 Modifications are required on the length of the flights for cells 9 and 10.
- 9. Elimination of Performance Test Lab Fees for all 10 cells (Credit) Due to logistical issues related to COVID-19 at the time of testing, AWC waived laboratory testing of the filter effluent samples for all cells. The initial results from the laboratory tests were acceptable and in place of delaying the project to conduct the testing, a credit was agreed upon.
- 10. Elimination of 24-inch Waste Gate Manual Operator (Credit) The manual operator provided by the vendor was too large for the location of the waste gate valves and did not comply with the specification. A credit was agreed upon.
- 11. Elimination of Blower Motor Thermostats (Credit) The motor temperature switch that was originally provide by the vendor did not comply with the cut sheet to measure ambient temperature. After discussions, the thermostat is not necessary on the blower motors due to the infrequent operation. In place of replacing all motors, a credit was agreed upon.
- 12. Elimination of Handrail The purpose of moving the handrail was to accommodate supports for the Blower Air Scour (BAS) Header Piping. Since the BAS piping is not located above this area, this modification is not necessary.
- 13. Unit Price Item U1 ALLOWANCE (Credit) Line Item U1 is not needed in its entirety



REQUEST FOR QUOTATION

	QUOTATION NO: PURAC-RFQ-03
TO: Rapid Pump & Meter Service Co., Inc.	DATE: 9/11/2020
FROM: Shivani Patel, PE	
PROJECT: NHSA PURAC System Upgrades, Phase 3 -	Loan S340952-30
KEYWORD DESCRIPTION: Skimmer Flight Cells	
DATE QUOTATION REQUIRED: 9/23/2020	
The following modification to the contract has been identified. quotation for the alteration as described in Item 1. The quotatic subcontractor costs, including labor, materials, rentals, approved considered authorization to proceed with the work herein described.	on should include an itemized breakdown of contractor and red services, overhead, and profit. This request shall not be
To be completed by Initiator of Request:	
Scope of Work: (include list of attachments) Modify the skimmer flight return wear blocks on Cells #3 and #4, as per RFI-035.	Could be a visual country to be a local to be a visual at (0) and be a beat for 0 all a 0.
Remove all FRP skimmer flights on Cells #3 and #4 and replace with new Marine-Grade Aluminum skimmer flights provided by AWC. Adjust flight wipers to conform to their respective beaches and	 Cut bearing support brackets and plug weld (2) anchor bolts for Cells 3 and 4. Install bumper guards along the top rails in Cells 3 and 4.
the cell walls. 3. Remove existing drive motor bases on Cells #3 and #4 and replace with new adjustable motor	 Provide all delivery truck unloading services. Furnish any necessary miscellaneous hardware.
bases provided by AWC. 4. Remove two "smooth" wheels from each side of all new aluminum flights. Replace with new "shouldered" wheels provided by AWC.	7. Full of any necessary interest factories.
The skimmer equipment supplier, AWC (who is under a separate supply contract design and motor bases. AWC undertook a redesign effort and had new items fa Contractor to perform the field work associated with the skimmer modifications. 3. Approval of Request: Owner:	
Engineer: Shivani Patel, PE	Date: 9/11/2020
To be completed by Contractor:	
Total cost of modification (attach detailed breakdown)	\$ \$22,536.42
5. Will a modification to the contract time be required?	Yes □No
If so, trade(s) Mil	llwright/Laborer
No. of personnel	
Duration 7	(calendar days)
6. Attachment identification: (list)	nange Order - WCD-01
7. Quotation is in effect until: (date)	
Approval of Quotation	
Contractor Steven Marsich, P.E.	Date09/23/2020
Copy:	



September 23, 2020

Mr. Dejan Davidovic Resident Engineer, North Hudson Sewerage Authority Jacobs 299 Madison Avenue Morristown, NJ 07960 Dejan.davidovic@jacobs.com

Reference: PURAC System Upgrades, Phase 3, Contract 4

North Hudson Sewerage Authority Notice of Amount and Extent of Claim

Proposed Change Order for Work Change Directive No. 1

Cells 3 and 4 Flight Modifications

PCO-WCD-01

Dear Mr. Davidovic:

Following to your Work Change Directive No. WCD-01 dated 12/19/19, Rapid Pump and Meter (RPM) have established the costs and time delays incurred in connection with the modification of flights in Cells 3 and 4.

Claim

In accordance with Article 10.05 of the General Conditions, RPM notes that the adjustment claimed is the entire adjustment to which we believe we are entitled as a result of this event.

Contract Defined Field Conditions

Contract Drawing 10382-04-01 Sheet 17 of 17 depicts a chain and flight assembly for skimmers utilized as part of the Owner-Furnished Equipment described in Specification Section 11100. This equipment was preselected by the Owner and provided by AWC Solutions of Surrey, BC, Canada.

Lump Sum Pricing Approach

As per the Contract Documents, Rapid Pump provided Lump Sum Pricing of \$1,866,000.00 for Item L13 – Furnish and Install Filter Equipment, Underdrains, and Media. This lump sum pricing assumed that the equipment would be delivered to site as depicted in the Contract Documents, and would be operational without need for substantial modification unless otherwise noted in the Contract Documents.

Mr. Dejan Davidovic September 23, 2020 Page 2 of 8

There was no indication in the Contract Documents that these flights would require modification in order to allow proper functional operation.

Summary of Relevant Events

Following is a summary of events relevant to the execution of work under this PCO:

- On 6/11/19, RPM issued RFI 035 (*Attachment 1*) noting conflicts in the flight hardware provided that would prevent the system from operating properly at Cells 3 and 4. Specifically, conflicts were noted between the "return wear blocks" mounted on the end of each flight and the shaft bearing mount assembly on the south side of each cell.
- On 6/12/19, Jacobs responded to the RFI 035 requesting that RPM modify two (2) blocks as directed by the manufacturer, AWC as a proposed trial solution.
- On 7/2/19, Jacobs issued a Work Change Directive (WCD-01 *Attachment 2*) authorizing modification of wear blocks on all 72 flights (36 flights per cell for Cells No. 3 and 4).
- Between 7/2/19 and 7/18/19, RPM removed the wear blocks from the existing flights, brought them to our shop in Paterson, NJ, modified the blocks, returned the blocks to site, and reinstalled.
- On 10/17/19, at Construction Progress Meeting No. 9, Jacobs notified RPM that AWC was redesigning and replacing the existing flights and motor mounts for Cells 3 and 4 (and all future cells). As directed by Jacobs, RPM agreed to install the modified equipment in anticipation of a future work change directive/work order (*Attachment* 3).
- On 11/4/19, the redesigned equipment was present at the site.
- Between 11/5/19 and 11/8/19, RPM installed modified equipment under the direct supervision of AWC representative Teunis Cloete.
- On 12/19/19, Jacobs issued a revised WCD-01 (*Attachment 4*) incorporating the installation of replacement equipment.

Price Adjustment Calculation

In accordance with General Conditions 12.01 B, an adjustment in the Contract Price is requested for lump sum of \$22,536.42 The basis for the price adjustment is included as *Attachment 5*.

Mr. Dejan Davidovic September 23, 2020 Page 3 of 8

Time Adjustment Calculations

In accordance with General Conditions 12.02 B, an adjustment in the Contract Time is requested for a total of one week (7 days). This is based on the dedicated use of 6 man mechanical crew during the week of 11/4, resulting in overall delay of 1 week.

Please let us know if you have any questions or need additional information.

Regards,

Steven Marsich, P.E. Rapid Pump & Meter Service Co., Inc.

Cc: Christina Lehr, Jacobs Steve Kulcsar, RPM

ATTACHMENT 1 RFI 035 June 11-12, 2020 P.O. Box AY • 285 Straight Street • Paterson, NJ 07509 • Fax (973) 345-0301 • **Phone (973) 345-5600** Emergency Service (201) 933-3569 • info@servicer.com



Request For Infor	mation/ RFI	RFI NO:	035
PROJECT: NHSA PURAC System Upgrades, Phase	3	PROJECT NO:	S340952-30
CONTRACTOR: Rapid Pump & Meter Service Co., In	nc. (Rapid)		
RFI Initiated By:	Steven Marsich, Rapid		
Regarding: Plan Sheet76 of132	Spec. Section: 11100	_	
Description:			

Skimmer Installation - Return Wear Block

While installing the skimmer rails at Cells 3 and 4, RPM have noted some conflicts that may prevent the skimmer from operating properly, specifically with the return wear block.

The following pages show three areas of conflict:

- 1. Cell 3 East side return wear block hits third anchor bolt
- 2. Cell 3 East side return wear block hits bearing bracket angle
- 3. Cell 3 West side return wear block hits bearing bracket angle

RPM has proposed some potential solutions below, but we require direction from Jacobs/AWC before any modifications are made. Additionally, modifications would be considered a change in the scope of work and additional costs would be incurred by RPM and a change order or claim would be required.

Steven Marsich, P.E.
Prepared by
6/11/19
Date


Response Assigned to:

See below attached response/drawings showing new dimensions for return block. Trim just (2)blocks as shown in the drawings attached. Once Blocks are trimmed install and test the flight travel over the sprocket.

Dejan Davidovic	
Signed	
06/12/2019	
Date	


Cell 3 East side - return wear block hits third anchor bolt






Potential Solutions:

- 1. Remove third anchor if AWC determines that placement of remaining two 1" anchors are sufficient
- 2. Trim return wear block reducing the height of the projection on the wear block by 1/2" as pictured below should avoid conflict with bolt. This would lower the overall elevation of the skimmer by the same distance when it is traveling on the upper rail. RPM would recommend modifying a single block and testing it in order to ensure the conflict is resolved.



Cell 3 East side - return wear block hits bearing bracket angle






Potential Solutions:

1. AWC has recommended trimming the bearing support bracket with a 1" x 1" notch on as pictured to the right. This solution does not appear to be sufficient as the block would appear to still hit the bearing housing.

t with a 1" x 1" notch on as cient as the block would appear

Notch

2. Trim return wear block – reducing the overall height of the wear block by 5/8" as pictured below should reduce conflict with the bracket. This would lower the size of the "step" used to keep the skimmer in place when it is traveling along the top rail. This modification could also be combined with the 1/2" modification of the projection proposed above which would largely maintain that step size. RPM would recommend modifying a single block and testing it in order to ensure the conflict is resolved.




Cell 3 West side - return wear block hits bearing bracket angle






Potential Solutions:


AWC has recommended trimming the bearing support bracket with a 1-1/2" x 1-1/2" notch on as pictured to the right. This solution does not appear to be sufficient as the block would appear to still hit the bearing housing. Please also note that the support bracket is 13" and not 12" as was indicated on the most recent drawing.



2. Trim return wear block – reducing the overall height of the wear block by 5/8" as pictured below should reduce conflict with the bracket. This would lower the size of the "step" used to align the skimmer as it is traveling along the top rail. This modification could also be combined with the 1/2" modification of the projection proposed above which would largely maintain that step size. RPM would recommend modifying a single block and testing it in order to ensure the conflict is resolved.



(8.1)



] /
-						١ '
REV	DESCRIPTION	BY	CHK'D	APP'D	DATE	

<u>NOTE</u>

THIS DRAWING IS THE PROPERTY OF AWC WATER SOLUTIONS, AND CONTAINS PROPRIETARY AND CONFIDENTIAL INFORMATION WHICH MUST NOT BE DUPLICATED, USED OR DISCLOSED OTHER THAN EXPRESSLY AUTHORIZED BY AWC WATER SOLUTIONS.



#104-19074 22nd Avenue Surrey, BC Canada V3Z 3S6
Phone: 604-638-0760 Fax: 604-638-0795
www.awcwater.com

DRAWN	WW	
DESIGN	CC	
CHECKED	CC	
APPROVED	JY	
DATE	2019-06-11	
SCALE	NONE	ı

NORTH HUDSON SEWERAGE WWTP


(PO. #10382)

AWC Model DAF/Flo-Filter WWTP

WEAR BLOCK MODIFICATION

SHEET 1 OF 1

DRAWING NO. 10382-04-06 REV -



]] ,
-						
REV	DESCRIPTION	BY	CHK'D	APP'D	DATE	

<u>NOTE</u>

THIS DRAWING IS THE PROPERTY OF AWC WATER SOLUTIONS, AND CONTAINS PROPRIETARY AND CONFIDENTIAL INFORMATION WHICH MUST NOT BE DUPLICATED, USED OR DISCLOSED OTHER THAN EXPRESSLY AUTHORIZED BY AWC WATER SOLUTIONS.



#104-19074 22nd Avenue Surrey, BC Canada V3Z 3S6
Phone: 604-638-0760 Fax: 604-638-0795
www.awcwater.com

DRAWN	WW	
DESIGN	СС	
CHECKED	CC	
APPROVED	JY	
DATE	2019-06-11	
SCALE	NONE	1

NORTH HUDSON SEWERAGE WWTP

(PO. #10382)

AWC Model DAF/Flo-Filter WWTP

WEAR BLOCK MODIFICATION

SHEET 1 OF 1

DRAWING NO. 10382-04-06 REV -

Mr. Dejan Davidovic September 23, 2020 Page 5 of 8


ATTACHMENT 2

WCD-01 revision 1 July 2, 2019



WORK CHANGE DIRECTIVE

TO CONTRACTOR: Rapid Pump & Meter Service Co., Inc.		WCD NO: 1			
PROJECT NHSA PURAC System Upgrades, Phase 3 PROJECT NO: S340952-30					
OWNER: North Hud	dson Sewerage Authority				
ENGINEER: JACOI	BS				
The following additions	s, deletions, or revisions to the Work have been ordered a	nd authorized:			
While installing the ski properly, specifically the	Description of Work: While installing the skimmer flights in Cells 3 and 4, Contractor observed conflicts that prevent the flights from operating properly, specifically the Return Wear Blocks. Skimmer flight Return Wear Blocks conflict with Bearing Support Bracket and Anchor Bolt. Contractor to trim Cell 3 and Cell 4 Return Wear Blocks as per attached AWC recommendation.				
Remove each	n of the 72 Flight Return Wear Blocks from all skimmer flig	hts in Cell 3 and 4.			
 Trim Blocks as recommended by AWC engineer – see attached AWC – Return Wear Block – Modification drawing. 					
	ly modified blocks to 36 Skimmer Flights for future installa	ntion for Cell 3 and 4			
Reason for Change(s There are (3) Location Bracket and Bearing S	s where the return wear blocks conflict with the Head Sha	t Bearing Housing, Bearing Support			
Cell West Wa	all - return wear block hits third anchor bolt				
Cell West Wa	all - return wear block hits bearing bracket angle/housing				
Cell East Wal	II – return wear block hits bearing bracket angle/housing				
The as-found condition	n of the Filter Cells post-demolition exceded the tolerances	of the skimmer equipment.			
Attachments (List Su	pporting Documents):				
AWC – Return Wear E	Block - Modifications				
It is understood that this Work Change Directive will not change the Contract Price or Times but is evidence that the parties expect a Change Order to be subsequently issued reflecting any changes.					
Ordered By: Michael Wilson 07/02/2019					
Ordered By:					
Recommended By:	Recommended By: Dejan Davidovic RE 07/02/2019				
	Engineer	Date			
Сору:					



] /
-] \
REV	DESCRIPTION	BY	CHK'D	APP'D	DATE	

<u>NOTE</u>

THIS DRAWING IS THE PROPERTY OF AWC WATER SOLUTIONS, AND CONTAINS PROPRIETARY AND CONFIDENTIAL INFORMATION WHICH MUST NOT BE DUPLICATED, USED OR DISCLOSED OTHER THAN EXPRESSLY AUTHORIZED BY AWC WATER SOLUTIONS.



#104-19074 22nd Avenue Surrey, BC Canada V3Z 3S6
Phone: 604-638-0760 Fax: 604-638-0795
www.awcwater.com

DRAWN	WW	
DESIGN	CC	
CHECKED	CC	
APPROVED	JY	
DATE	2019-06-11	
SCALE	NONE	[

NORTH HUDSON SEWERAGE WWTP

(PO. #10382)

AWC Model DAF/Flo-Filter WWTP

WEAR BLOCK MODIFICATION

SHEET 1 OF 1

DRAWING NO. 10382-04-06 REV -

Mr. Dejan Davidovic September 23, 2020 Page 6 of 8

ATTACHMENT 3

Construction Meeting No. 9 Minutes October 17, 2019



Meeting Minutes

North Hudson Sewerage Authority 1600 Adams Street, Hoboken, New Jersey

Subject Construction Meeting No. 9 - Meeting Minutes

Project Name NHSA PURAC System Upgrades Phase 3 – Contract 4

Project Number S340952 - 30

Prepared by Dejan Davidovic, Resident Engineer

Date 12/20/2019

Participants See attached sign in sheet.

Copies to OMI, Rapid Pump, NHSA, NJDEP

On October 17th, 2019 a construction meeting was held at the Authority's Adams Street WWTP for the above referenced project. Representatives from Jacobs (CH2M), OMI and Rapid Pump & Meter Service Co., Inc (Rapid/Contractor) were in attendance. Attached is an agenda and attendance list from the meeting.

Please return comments to Dejan Davidovic / Jacobs, within five days of receipt. Otherwise, the meeting minutes will be considered complete and accurate as written.

NTP ISSUED ON	August 27, 2018	
No. of Days Elapsed	416 Days (45%)	October 17, 2019
Substantial Completion	860 Days	January 3, 2021
Final Completion	920 Days	March 4, 2021

Notes	Action
1 Construction Progress to D	Successfully completed the Air/Water test on Cells 3 and 4 underdrains.
	 Loaded gravel and media into Cells 3 and 4 under AWC's supervision. (AWC media signoff pending OMI's grout repairs at Cell #4 Orifice plate.)
	 Completed Electrical installation of RGS conduits to Effluent Valves, Slide Gates, DPIT's, Waste Gates and Skimmer control panel.
	 Completed the wire pulls and terminations for all Cell 3 and 4 Effluent Valves, Slide Gates, DPIT's, Waste Gates and Skimmer control panel.
	• Systems Integrator OCC installed new PLC equipment in Panels CP-1, CP-4, and CP-4B.
	• OCC started the terminations and wiring of HOA's at panel CP-1.
	OCC started the programing of new PLC's working closely with Kyle Arnold of OMI.
	Continued installing 12" BAS piping, supports and Blower Valves.



Notes		Action
		Completed the cleanout of Saturation Tank's No. 1 and No. 2.
		Started Up Blower No. 1 - manufacturer was present.
2	Potential Change Orders	Jacobs will not be sending a letter response letter to Rapid's inquiry on PCO#1 status. The status of sand removals from filter cells will be tracked and monitored as the work progresses.
		Jacobs reiterated the importance of measuring and tracking sand levels in cells #9 and #10. Total quantity of sand in the filter cells needs to be quantified.
		It was discussed that the sand levels in all remaining cells to be demolished should be measured at this time and an overall assessment made. Measurements will have to be a coordinated effort between Jacobs, Rapid, and OMI.
3	Change Orders	None to date
4	Field Orders	None to date
5	Work Change Directives	WCD #1 – Skimmer Return Wear Block Modifications, Cells #3/4. Jacobs will prepare and transmit to Rapid.
		WCD – Filter Plenum Air Release Valves – Jacobs informed havin a means to expel air from the filter plenum area may be beneficial however, will not be performed on Cells #3 and #4. Jacobs will inquire with AWC and DeNora about the concept.
6	Request for Information	RFI 040 – Cable Tray Feeders – Resolved RFI 041 – Blower LCP – Responded
7	Request for Quotations	None to date
8	AIS (American Iron and Steel)	05500-003-2 - Platform and Trough Support Beams -Outstanding
		05500-005-1 - Metal Bar Grating - Outstanding
		11341-001-2 - Baffle Walls – Outstanding. Need letter on Anchors
		Contractor to make use of De minimis waiver. Per Contractor Anchors arrived with equipment thus part of assembly. Jacobs to research and confirm availability of AIS compliant anchor rods manufacturers.
		15200-002-1 - Carbon Steel Pipe and Fittings - Outstanding
		11282-001-3 - Fabricated Gate – Outstanding. Need letter on Anchors.
		15200-006-1 - Basket Strainer - Outstanding.
		15200-010-1 - Steel Coupling – Outstanding.
		15200-012-1 - DI and Galvanized Piping SPEW
9	SED	Quarterly Reports are up to date. Jacobs advised that monthly reports are no longer needed if Rapid Pump achieves the agreed upon utilization SED goal of 12.9%.
		Quarterly SED report was submitted to NJDEP.
10	Administrative Submittals	Detailed Progress Schedule – Not received – Submit formally with official transmittal. Updated Progress Schedules – Not received -Submit Monthly with official transmittal. Contractor stated that most recent schedule wa to the end of the project.



Notes	Action
	Jacobs inquired on schedule updates protocol and distribution specific to Cells 3 and 4. Contractor advised being ready for Functional Test of Cells 3 and 4 on 10/21.
11 Shop Drawing Submittals	Field Acceptance Test Plan – RR
	Copper Piping Layout – RR
	SPEW Piping Layout – RR
	Aluminum Metal Railing – RR
	Process Control Software – Outstanding - Contractor to confirm OMI Maintenance manager has the same software program used by OCC's system integrator programmer.
	SCADA HMI display screens submittal
12 Permits	Electrical – Sam Abma of Rapid Pump inquired with permitting office at City of Hoboken. However, did not schedule an electrical inspection. Rapid will inquire with Code Office again.
	Building – Completed one on-site inspection with City of Hoboken Code office. Per Code Office inspection of next slab pour is waived However, Jacobs to maintain and have available all special inspection reports for City inspector's review.
13 Project Quality	Owner furnished Special Inspections are ongoing and will continue for specific items of work; anchors, steel platform, and slab in-fill.
	Contractor Quality Control: Contractor to provide work plan identifying all Contractor Furnished QC for the project. Jacobs and Rapid to jointly review the specifications.
14 Health and Safety	Contractor is responsible for site Safety.
	AHA and Work Plan required for major work activities and confined space entry.
	Jacobs requested signed AHA used on 07/02 during the incident with temporary 12" Saturation hose connection.
15 General Project Information	Contractor confirmed some LP Blocks are stored on site, but not all. To inquire with main office of remaining Cell #9 and #10 equipment stored off site. Special end units are of interest.
16 Potential Construction Issues	Electrical installations required for Cells 3 and 4 startups.
	OCC submittals, programming, wiring installations, and field testing
	Process valves testing – Jacobs to issue punch-list.
	Filter underdrains grout repair at orifice plate. Grout curing in Cell 4. Jacobs to verify when the next grout breaks will be performed.
	Certificate of proper installation: Influent gates and actuators, Blowers and Blower Safety devices, BAS Air Header unloading valve, DeZurik Valves, etc.
	Jacobs requested Contractor to submit on outstanding Blower monitoring devices for review and approval.
17 Owner-furnished equipment	Jacobs requested detailed inventory of media damaged prior to installation and quantities remaining in storage. Rapid Pump confirmed list of stored media already created. Rapid Pump to distribute media inventory currently on site.
	AWC media installation sign off. Requires confirmation of Orifice Plate Grout repair in Cell #4.



Notes	Action
	AWC redesigning flights, wipers and motor mount bases. Anticipate
	shipment on October 29th with receipt on site on November 4th.
	Jacobs advised Cell 3 grout repairs not necessary at this time. Rapid Pump requested WCD or CO from Jacobs on motor base work and skimmer flights replacement in both Cells 3 and 4. Jacobs agreed to issuing a WCD for Cells 3 and 4 flights replacement and motor base swapping.
	AWC finalizing 48-hr Performance Test Procedure for Jacobs review/approval; update expected 10/18/2019.
	After successful 48-hr performance there is a (1) Week Acceptance test. Specification was reviewed and the 1 week acceptance test is when all 10 cells are complete, not for each set of cells.
18 Open Discussion	Rapid Pump requested WCD regarding toggle style disconnect switches for new equipment and valves in PURAC. So the switches can be made to be lockable. Jacobs agreed new lockable cover plates are needed.
	Rapid Pump advised current Media Super-sacs are not UV resistant and susceptible to breaking due to sun exposure while stored at vendor facility. Jacobs will inquire with AWC to verify if the supersacks for the entire project are at DeNora's warehouse, or not.
	Jacobs inquired on OCC's plan for testing and wiring and programing on site. Once Cells 3 and 4 mechanically and electrically complete, how is OCC planning to test the whole system with new equipment on line
	Existing level transmitters will be reinstalled in Cells #3 and #4. OMI will assist to recalibrate the new transmitters. All to verify if the cells need to be filled with water to perform the calibration.
	Rapid requested the AWC-furnished recycle pipes for Cell #10 and the balance of the underdrain blocks. Jacobs will confirm and coordinate with AWC on the fabrication and shipments for Cells #9 and #10.
	Jacobs to confirm the weir elevations for the backwash troughs in cells #3 and #4.
	Terry (PLC programmer from OCC) will be on-site all next week. He is ready to perform a PLC program upload today.
	DeZurik was on site yesterday for the newly installed valves. They should be providing the certificates of proper installation today.
	Influent gates for Cells #3 and #4. The manufacturer's representative needs to come to the project site for startup and testing. Rapid needs to confirm their availability and schedule them to be on site.

Mr. Dejan Davidovic September 23, 2020 Page 7 of 8

ATTACHMENT 4

WCD-01 FINAL December 19, 2019



WORK CHANGE DIRECTIVE

TO CONTRAC	FOR: Rapid Pump & Meter Service Co., Inc.	WCD NO: PURAC-WCD-01
PROJECT:	PURAC System Upgrades, Phase 3 – Loan S340952-30	PROJECT NO:
OWNER:	North Hudson Sewerage Authority	
ENGINEER:	Jacobs	
The following a	dditions, deletions, or revisions to the Work have been ordered and au	uthorized:
Description o	Work:	
 Modify the Remove a AWC. Ad Remove e Remove to AWC. Cut bearing and 4. Provide al 	evisions to the work are authorized: skimmer flight return wear blocks on Cells #3 and #4, as per RFI-035. I FRP skimmer flights on Cells #3 and #4 and replace with new Marine ust flight wipers to conform to their respective beaches and the cell waxisting drive motor bases on Cells #3 and #4 and replace with new adjute of "smooth" wheels from each side of all new aluminum flights. Replace g support brackets and plug weld (2) anchor bolts for Cells 3 and 4. Instelligence truck unloading services. I FRP skimmer flight return wear blocks on Cells #3 and #4 and replace with new Adjute of "smooth" wheels from each side of all new aluminum flights. Replace g support brackets and plug weld (2) anchor bolts for Cells 3 and 4. Instelligence truck unloading services. I FRP skimmer flight return wear blocks on Cells #3 and #4 and replace with new Adjute of "smooth" with the cell wax and "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of "smooth" wheels from each side of all new aluminum flights. Replace of the flight wheels from each side of all new aluminum flights.	e-Grade Aluminum skimmer flights provided by alls. ustable motor bases provided by AWC. ce with new "shouldered" wheels provided by
of their FRP-ba	quipment supplier, AWC (who is uder a separate supply contract with sed flight design and motor bases. AWC undertook a redesign effort at is necessary for the Phase 3 General Contractor to perform the field	and had new items fabricated at no charge to
Attachments	List Supporting Documents):	
None		
	that this Work Change Directive will not change the Contract Price or to be subsequently issued reflecting any changes.	Times, but is evidence that the parties expect a
Ordered By:	Owner	Pote
Recommended Copy: Owner Engineer	By: John V. Tobia, PE Engineer	Date 12/18/2019 Date
AWC Electronic F	les	

Mr. Dejan Davidovic September 23, 2020 Page 8 of 8

ATTACHMENT 5

Cost Calculations

Des	cription: PCO Cost Breakdown				
1.	Payroll Costs: Trade See page 2 of Proposal		<u>Hours</u>	Rate \$ \$ \$	Total 18,227.32 - - -
				SUBTOTAL: \$	18,227.32
2.	Material & Permanent Equipment: See Page 3 of Proposal			\$	250.00
				SUBTOTAL: \$	250.00
3.	Subcontractor Work:	Price	Qty.		
				\$	-
				\$ \$	-
				\$	-
				SUBTOTAL: \$	-
4.	Supplement Costs:				
	a. b.			\$ \$	-
	c. d.			\$ \$	-
	e.			\$	-
	f. g.			\$ \$	-
	h. i.			\$ \$	-
	j.			\$	
				SUBTOTAL: \$	-
5.	Grand Total (Subtotal 1, Subtotal 2, Subtotal 4, Subtotal 5):			\$	18,477.32
	Contract Decrease				
6.	Contractor Credit			\$	-
	Net Contract Increase				
7	Direct Work Sub-Total (Increase 5 + Decrease 6)			\$	18,477.32
8	Contractor's Overhead (10%): Contractor's Profit (10%):			\$ \$	1,847.73 2,032.51
9	Subcontractor Total (Item 3 Subtotal)			\$	-
10	Subcontractor Markup (10% of Item 10 total)			\$	-
11	Bond Premium (0.8% x Lines 8,9):			\$	178.86
12	TOTAL INCREASE:			\$	22,536.42

LABOR/MATERIALS BREAKDOWN

Labor

	<u>Men</u>	<u>Days</u>	Hrs/ Day	<u>Total</u> <u>Hours</u>	Rate Category	<u>Rate</u>		<u>Total</u>		
RPM Labor Services - WCD 01 - Ju	RPM Labor Services - WCD 01 - July 2019									
Task - Modify Wear Blocks Straight Time										
Supervision	1	2	4	8	Millwright	\$ 89.29	\$	714.36		
Block Removal/ Installation	2	2	4	16	Laborer	\$ 70.16	\$	1,122.56		
Pickup/Delivery	1	2	4	8	Laborer	\$ 70.16	\$	561.28		
Block Cutting	1	3	4	12	Laborer	\$ 70.16	\$	841.92		
RPM Labor Services - WCD 01 - November 2019 Task - Replace Existing Equipment with Modified Equipment Straight Time										
Support Supervision	1	4	8	32	Millwright	\$ 89.29	\$	2,857.44		
Support Labor	5	4	8	160	Laborer	\$ 70.16	\$	11,225.64		
Overtime (x 1.5)										
Support Supervision	1	3		6.75	Millwright	\$ 133.94	\$	904.11		
Support Labor	5	1	3.75	18.75	Laborer	\$ 105.24	\$	1,973.26		

TOTAL LABOR \$ 18,227.32

LABOR/MATERIALS BREAKDOWN

Materials & Equipment

	<u>Unit</u>	<u>Qty</u>	<u>Each</u>	<u>Total</u>
Delivery Truck - Pickup Delivery Truck - Return	Day Day	0.5 0.5	250 250	125 125
TOTAL				\$ 250.00

Trade Laborer	C	ontract Begins	5/1/2018
	S	traight	
		<u>Time</u>	
1 Base Hourly wage	\$	34.05	
O Dive Veresties Dev			
2 Plus Vacation Pay			
3 Plus other taxable items			
4 Taxable base	\$	34.05	
5 Plus Workmen's Compensation(8.51% of 4)	\$	2.90	
6 Plus Fringe Benefits	\$	28.02	
9 Subtotal	\$	64.97	
10 Plus FICA(7.65% of 4)	\$	2.60	
11 Plus FUTA(0.6% of 4)	\$	0.20	
12 Plus SUI(2.0% of 4)	\$	0.68	
13 Subtotal	\$	68.46	
14 Plus G.L & P.D.(5.00% of 4)	\$	1.70	
15 Total Labor Rate	\$	70.16	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Trade	Electrician	Co	ontract Begins	12/8/2017
		S	Striaght	
			<u>Time</u>	
	1 Base Hourly wage	\$	41.84	
	0. DL . V . V . D			
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	41.84	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	3.56	
	6 Plus Fringe Benefits	\$	21.97	
	9 Subtotal	\$	67.37	
	10 Plus FICA(7.65% of 4)	\$	3.20	
	11 Plus FUTA(0.6% of 4)	\$	0.25	
	12 Plus SUI(2.0% of 4)	\$	0.84	
	13 Subtotal	\$	71.66	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.09	
	15 Total Labor Rate	\$	73.75	
	0	Ψ	. 5 6	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Trade	Millwright	C	ontract Begins	5/1/2018
		S	triaght	
			Time	
	1 Base Hourly wage	\$	48.80	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	48.80	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	4.15	
	6 Plus Fringe Benefits	\$	28.90	
	9 Subtotal	\$	81.85	
	10 Plus FICA(7.65% of 4)	\$	3.73	
	11 Plus FUTA(0.6% of 4)	\$	0.29	
	12 Plus SUI(2.0% of 4)	\$	0.98	
	13 Subtotal	\$	86.85	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.44	
	15 Total Labor Rate	\$	89.29	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Rapid Pump & Meter Service Co., Inc.



Remit to: PO Box AY Paterson, NJ 07509

Customer Contact

Kim Wilson

Contact Phone#

(720) 286-2750 x

Service Report

Job Number

RC40043

Customer PO#:

SO340952.30

www.rapidservice.com **Customer Information**

Ph; 973.345,5600

Fx: 973.345.0301

Location Information

North Hudson Sewerage Authority Adams Street P.O. Box 6607

ENGLEWOOD, CO 80155

1600 Adams Street HOBOKEN, NJ 07030 Payment Terms:

Net 10

Priority:

Standard

7/16/2018

ENGLEWOOD, CC (201) 963-6043 x Required Work	80155 HOBOKEN	, NJ 07030	Su	Schedul Eq pervisor/Techi	uip ID:	7/16/2018 () \tag{\tag{\tag{\tag{\tag{\tag{\tag{
	ade, Phase 3 Physical Syst	em Improven	nent, as per Co	ontract.		
Otv	Part or Description	<u> </u>		Joh Des	scription	
Gry Mate Car Mise	600A-230P -	\$ £	7051 5751	# 3 q	√	Recycles
Told signe 13 Miles Dan M	6°0A-2308 - 6°0A-2308 - 6°0A-110°04	F 5	Track		•	
		- C - C - P	out condu	on was	e eic.	scor Lo- 6-10 mcc lues + Alrdyer
workers x 8 supervisor x	Section N			mmencement		
supervisor x	Requirements:	Lockout/T	agout Hot	work Permit	Confined s	space Fall Protection
		Communic		er for on-site safe	ty protoco	
Date	Technician SKelly MIRFA PETEK KNIS K CHAIS K TASON C	8 8 8 8 9	Time In 6 (0) 600 600 600 600	732 734 734 730 730 730	Field Shop	Sheet # 264 Job Status Incomplete Complete Printed 10/31/2019
Technician (I	PRINT NAME):					Date: 1/4/19
Received by (I	PRINT NAME):					Date:

Rapid Pump & Meter Service Co., Inc.



Customer Contact

Kim Wilson

Contact Phone#

(720) 286-2750 x

Service Report

Job Number

RC40043

Customer PO#:

SO340952.30

Customer Information

Location Information

North Hudson Sewerage Authority Adams Street

P.O. Box 6607

ENGLEWOOD, CO 80155 (201) 963-6043 x

Adams Street 1600 Adams Street HOBOKEN, NJ 07030 Payment Terms:

Net 10

Priority:

Standard

Schedule Date:

7/16/2018

(201) 963-6043 x			Su	Equ pervisor/Techn	-	E40061			
Required Work	rade, Phase 3 Physical System	Improvem							
r drae dystem opg	nade, i fiase e i fiyeleal eyetem		, ,						
6 WOL	rkers x 8 hours			Job Des	cription				
	ervisor x 9.25 hours	-Car	- Cont work on a'r scor giping - Cond work on Conduits in Mcc						
I sup	ervisor x 5.23 flours	10	and Oorl	con Condi	175 10	mee			
	3-1-1								
	Chair	/ 4	/33 .	<u> </u>	. ~~				
	Christ Krisk	(000 -	730	<u> </u>					
	PB10 H	(00 -	278	8	AND DESCRIPTION OF THE PERSON	`			
	mike A	600 -	230	£	estra.				
	JASON C	100	230	£-					
	S Kelly	100 7	345	<u>d</u>	1.59	And the first transfer of the state of the s			
		660	7-7300		SZ76	(6707) 1			
	***Safety Section MUS			ommencement of E on-site & in good		/es No initial			
Hazard assessmer									
Check	Applicable Safety Requirements:				Confined space	☐ Fall Protection			
		Communic	ate with custon	ner for on-site safet	y protocol				
Date	Technician		Time In	Time Out					
11/7/19	Gory Me JR 8.	76	00 A	245P					
11/	Con Ma SIL	- F/G	004	245P		Sheet # 263			
	Tollyne 13	6	000	234	J	ob Status			
	White S	(or a	2306	Field 🗸	Incomplete			
					Shop	Complete			
-					┧ ・ └──	nted 10/31/2019			
					1				

Technician	(PRINT NAME):	Date:	11/2/19
	(DOINE NABET)	Date:	7 /
Received by	(PRINT NAME):	Date.	

Rapid Pump & Meter Service Co., Inc.



Ph: 973.345.5600 Fx: 973.345.0301 www.repidservice.com Remit to: PO Box AY Paterson, NJ 07509

Customer Contact

Kim Wilson

Contact Phone#

(720) 286-2750 x

Service Report

Job Number

RC40043

Customer PO#: SO340952.30

Customer Information

Location Information

North Hudson Sewerage Authority Adams Street P.O. Box 6607

Received by (PRINT NAME):

ENGLEWOOD, CO 80155 (201) 963-6043 x

1600 Adams Street HOBOKEN, NJ 07030 Payment Terms:

Net 10

Priority:

Standard

Schedule Date:

7/16/2018

RCE40061

Date:

Required	Work
----------	------

equired Work		Supe	ervisor/Technician:	. NGE40001
	grade, Phase 3 Physical System Im	provement, as per Cont	ract.	
Qty	Part or Description		Job Description	on
Gty	Turto: Bootington	- Court consoluit	woh on com	
		forhs	Cot of the Cotto	
an and the second secon			on ince room	a conduit of
5 workers x	9 hours	A Come		
		- Shotdown of	How merter	to ruise walnt
1 supervisor	r x 9.75 hrs	Cope su	a to cells 6.	-10
		· · ·		
	MA I See A	600 - 2	33 - E	hugh.
	MIKEA		15 f	and Surf
	5100 C		70 8	
	Charle		70 8	
Township of the state of the st	Kail H	······································	ا کی کی ا	
	P 676 14	600 -	230	
	***Safety Section MUST			
Hazard assessmer			on-site & in good Condit	
Check	Applicable Safety Requirements:	ockout/Tagout Hotwo	ork Permit	d space Fall Protection
	□ c _c	ommunicate with customer	for on-site safety protoc	col
Date	Technician	Time In	Time Out	
11/6/19	Gary McJR &-		245P	
1111	10 Jun 607 Pm		245P	Sheet # 262
	JoOanne B		2300	Job_Status
	Dan in		1.30 P	
	M.kes 8	GerA 3	130P Field Sho	
			- Cilo	Printed 10/31/2019
	AND THE RESERVE OF THE PROPERTY OF THE PROPERT			Fillited 10/3 // 2013
<u> </u>				Date: 1/6/10
Tochnician ((DDINT NAME).			Date. 11/6/110

Rapid Pump & Meter Service Co., Inc.



Ph; 973.345.5600 Fx: 973.345.0301 Remit to: PO Box AY www.rapidservice.com Paterson, NJ 07509 **Customer Contact**

Kim Wilson

Contact Phone#

(720) 286-2750 x

Service Report

Job Number

RC40043

Customer PO#:

SO340952.30

Customer Information

Location Information

North Hudson Sewerage Authority Adams Street

Received by (PRINT NAME):

P.O. Box 6607 ENGLEWOOD, CO 80155

(201) 963-6043 x

1600 Adams Street HOBOKEN, NJ 07030 Payment Terms:

Net 10

Priority:

Standard

Schedule Date:

7/16/2018

Date:

(201) 903-0043 X		0	-	uip ID: RCE40061
Required Work	Discouling Contemporary		upervisor/Techn	ician:
Purac System Upg	rade, Phase 3 Physical System Improv	ement, as per C	ontract.	
Qty	Part or Description		Job Des	cription
~		-Court wo	honair	Scour & Comp
	11.75 hours r x 11.75 hrs	pining - Cent to	Pull some	ols for compressors
	MING COO SHALLY COO PCTON 600 Chair COO Kais COO ***Safety Section MUST com		615	32/ 32/ 32/ 32/ 32/ 32/
Hazard assessmen			E on-site & in good	
Check	Applicable Safety Requirements: Lockou	ut/Tagout	twork Permit 🔲 (Confined space
	Commo	unicate with custor	ner for on-site safet	y protocol
Date	Technician	Time In	Time Out	
1:/5/.7	Gaylack 65 - Talayas & Jan in & Wilsis &	600A 600A 600A 600A	3:00P 12:30P 230P 230P 230P	Sheet # 261 Job Status Field Incomplete Shop Complete Printed 10/31/2019
Technician (PRINT NAME):			Date: ///5//9



REQUEST FOR QUOTATION

	QUOTATION NO: PURAC-RFQ-04
TO: Rapid Pump & Meter Service Co., Inc.	DATE: 9/11/2020
FROM: Shivani Patel, PE	
PROJECT: NHSA PURAC System Upgrades, Phase 3 - Loan	n S340952-30
KEYWORD DESCRIPTION: Filter Cell Transmitters	
DATE QUOTATION REQUIRED: 9/23/2020	
The following modification to the contract has been identified. Pursiquotation for the alteration as described in Item 1. The quotation sh subcontractor costs, including labor, materials, rentals, approved so considered authorization to proceed with the work herein described	nould include an itemized breakdown of contractor and ervices, overhead, and profit. This request shall not be
To be completed by Initiator of Request:	
1. Scope of Work: (include list of attachments) 1. Furnish and install Qty. 10: Endress+Hauser Micropilot FMR51 radar- 3. Furnish and Install Qty. 10: Endress+Hauser Micropilot FMR51 radar- 3. Furnish and Install Qty. 10: Endress+Hauser Micropilot FMR51 radar- 3. Furnish and Install Qty. 10: Endress+Hauser Micropilot FMR51 radar- 3. Furnish and Install Qty. 10: Endress+Hauser Micropilot FMR51 radar- 3. Furnish and Install Qty. 10: Endress+Hauser Micropilot FMR51 radar- 3. Furnish and Install Qty. 10: Endress+Hauser Micropilot FMR51 radar- 3. Furnish and Install Qty. 10: Endress-Hauser Micropilot FMR51 radar- 3. Furnish And Install Qty. 10: Endress-Hauser Micropilot FMR51 radar- 3. Furnish Radar- 4. Furnish Radar- 5. Furnish Radar- 5. Furnish Radar- 6. Furnish Radar- 8. Furnish Radar- 9. Furnish Radar-	Furnish and install Qty. 10: custom mounting brackets. Refer to attached Jacobs bracket design sketch and level transmitter dimensional drawings.
based level transmitters. One (1) for each DAF/Filter cell. Refer to attached quotation. Order one (1) transmitter with an expedited fabrication/ship schedule. 4.	Provide manufacturer's representative's field startup, testing, and training for the new level instruments. Estimate the startup of 10 level instruments with be
 Furnish and install Qty. 10: Endress+Hauser Bluetooth modules (BT10), Model No. 71377355. Factory install one (1) BT10 module in each radar-based level transmitter. Refer to attached quotation. 	concurrent with training of plant operations and maintenance staff. Estimate (2.5) 10-hour days. Refer to attached manufacturer's representative's quotation. Provide shop drawing submittals for Engineer's review and approval, prior to purchase or manufacture.
	n Conditions(site, weather, etc)
The contract documents require the reuse of the existing level transmitters in the newly rehabilitated filter cells. However Jacobs is not confident the existing instruments will be reliable for long-term filter operations. Therefore, we recommend	I their replacement with a new level-instument with a more concentrated "beam angle" which will
ensure the instrument works better in the rehabilitated cells and will also work with the agitated foam-filled water surface 3. Approval of Request:	tnat occurs during backwasn.
Owner:	Date:
Engineer: Shivani Patel, PE	Date: 9/11/2020
To be completed by Contractor:	
	53,116.83
4. Total cost of modification (attach detailed breakdown) \$	33,110.03
5. Will a modification to the contract time be required?	es 🖺 No
If so, trade(s)	
No. of personnel	
Duration	(calendar days)
6. Attachment identification: (list) Cost Breakdown	, Equipment Specification, Design Sketch
7. Quotation is in effect until: (date)	
8. Approval of Quotation	
Contractor Steve Marsich, P.E.	Date 9/23/20
Copy:	Date9/23/20

Des	scription: WCD-03 - Filter Cell Level Transmitters		
1.	Payroll Costs: <u>Trade</u> Days Rate		Total
	Trade Days Rate See page 2 of Proposal for breakdown Installation of Ten (10) brackets and transmitters 1 \$1,403.21	\$	1,403.21
	* -	\$	-
	Sub Total (Labor durations are estimated - actual hours/days	may vary) \$	1,403.21
2.	Material & Permanent Equipment:		
	PCS Pump and Process, Inc Ten (10) new level transmitters Model FMR51-AAACADBDA5RGJ W.H. Kassner, Inc Ten (10) new brackets per Jacobs direction	\$	38,610.00 \$3,885.00
	SI	UBTOTAL: \$	42,495.00
3.	Subcontractor Work: Price Qty.	Φ.	
		\$ \$	-
	Sub Total	\$ \$	-
4.	Special Consultants:		
		\$	-
		\$	-
		\$ <u>\$</u>	-
	Sub Total (Consultant durations are estimated - actual hours/days may var	(y) \$	-
5.	Supplement Costs:		
	a. Painting Equipment	\$	-
	b. Welding Supplies c. Equipment Rentals:	\$ \$	-
	d. NA	\$	-
	e. NA f. NA	\$ \$	-
	g. As-Builts	\$	-
	h. Office Trailer Expenses i. Cad Design	\$ \$	-
	j. Bonds & İnsurance Adjustment:	\$	-
	SI	UBTOTAL: \$	-
6.	Grand Total (Subtotal 1, Subtotal 2, Subtotal 4, Subtotal 5):	\$	43,898.21
	Contract Decrease		
7.	Contractor Credit	\$	-
	Net Contract Increase		
8	Direct Work Sub-Total (Increase 6 + Decrease 7)	\$	43,898.21
9	Contractor's Overhead (10%): Contractor's Profit (10%):	\$ \$	4,389.82 4,828.80
10	Subcontractor Total (Item 3 Subtotal)	\$	-
11	Subcontractor Markup (5% of Item 10 total)	\$	-
12	Bond Premium (0.8% x Lines 8,9):	\$	-
13	TOTAL INCREASE:	\$	53,116.83

LABOR BREAKDOWN

	<u>Men</u>	<u>Days</u>	Hrs/Day	Total Hours	Rate	<u>Amount</u>	<u>Total</u>
Labor Services for installation of ten	(10) brad	kets					
Laborer Rate for installation (2 hour	s per brad	cket)					
	1	10	2	20	Laborer Subtotal	\$ 70.16 <u>\$</u>	1,403.21 1,403.21
	0	0	0	0	Laborer Subtotal	\$ 70.16 <u>\$</u>	<u>-</u>

NOTES:

Materials & Equipment

materials & Equipment	<u>Unit</u>	<u>Qty</u>	<u>Each</u>	<u>Tota</u>	<u>al</u>
See Summary Page				\$	-
TOTAL				\$	_

Trade	Laborer	C	ontract Begins	5/1/2018
		S	straight	
			Time	
	1 Base Hourly wage	\$	34.05	
	O. Dhua Maratian Davi			
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	34.05	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	2.90	\$ 73.98
	6 Plus Fringe Benefits	\$	28.02	\$ 76.48
	9 Subtotal	\$	64.97	\$ 2.50
	10 Plus FICA(7.65% of 4)	\$	2.60	
	11 Plus FUTA(0.6% of 4)	\$	0.20	
	12 Plus SUI(2.0% of 4)	\$	0.68	
	13 Subtotal	\$	68.46	
	14 Plus G.L & P.D.(5.00% of 4)	\$	1.70	
	15 Total Labor Rate	\$	70.16	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Trade	Electrician	Co	ontract Begins	12/8/2017
		S	Striaght	
			Time	
	1 Base Hourly wage	\$	41.84	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	41.84	
	5 Plus Workmen's Compensation(8.51% of 4)	-	3.56	
	6 Plus Fringe Benefits	\$	21.97	
	9 Subtotal	\$	67.37	
	10 Plus FICA(7.65% of 4)	\$	3.20	
	11 Plus FUTA(0.6% of 4)	\$	0.25	
	12 Plus SUI(2.0% of 4)	\$	0.84	
	13 Subtotal	\$	71.66	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.09	
	15 Total Labor Rate	\$	73.75	
	0			


^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Trade	Millwright	С	ontract Begins	5/1/2018
		S	Striaght	
			<u>Time</u>	
	1 Base Hourly wage	\$	48.80	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	48.80	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	4.15	
	6 Plus Fringe Benefits	\$	28.90	
	9 Subtotal	\$	81.85	
	10 Plus FICA(7.65% of 4)	\$	3.73	
	11 Plus FUTA(0.6% of 4)	\$	0.29	
	12 Plus SUI(2.0% of 4)	\$	0.98	
	13 Subtotal	\$	86.85	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.44	
	15 Total Labor Rate	\$	89.29	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%





January 3, 2020

Quote # 20191119-122MH r2

To: Steven Marsich, Rapid Pump and Meter

Subject: FMR51 Radar Level for tanks at North Hudson Sewerage Authority

PCS Pump & Process is pleased to offer the following equipment for your consideration.

One (1) Micropilot FMR51 (FMR51-AAACADBDA5RGJ)

- Approval: Non-hazardous area
- Power Supply; Output: 2-wire; 4-20mA HART
- Display, Operation: SD02 4-line, push buttons + data backup function
- Housing: GT19 Dual compartment, plastic PBT
- Electrical Connection: Thread NPT1/2, IP66/68 NEMA4X/6P
- Antenna: Horn 100mm/4"
- Seal: FKM Viton GLT, -40...150oC/-40...302oF
- Process Connection: Thread ANSI MNPT1-1/2, 316L
- Estimated production time 5 days per EQI expedite order arranged 11/18/19
- Expedited shipping included.

Price \$ 3,366.63

Nine (9) Micropilot FMR51 (FMR51-AAACADBDA5RGJ)

- Approval: Non-hazardous area
- Power Supply; Output: 2-wire; 4-20mA HART
- Display, Operation: SD02 4-line, push buttons + data backup function
- Housing: GT19 Dual compartment, plastic PBT
- Electrical Connection: Thread NPT1/2, IP66/68 NEMA4X/6P
- Antenna: Horn 100mm/4"
- Seal: FKM Viton GLT, -40...150oC/-40...302oF
- Process Connection: Thread ANSI MNPT1-1/2, 316L
- Estimated production time 11 days.
- Standard shipping included.

Price \$ 29,714.67

(10) Bluetooth module (BT10) (71377355)

- Module for wireless data communication.
- Usage: FMP50/FMP51/FMP52/FMP53/FMP54/FMP55/FMP56/FMP57, FMR50/FMR51/FMR52/FMR53/FMR54/FMR56/FMR57/FMR60/FMR62/FMR67.

Standard shipping included

Price \$1,153.84

Field startup, testing, training

- Startup of ten instruments with concurrent testing and training of operators.
 - o Estimated to take (2.5) 10-hour days at \$175/hr.
 - O No more than 5 total visits to the site, at a minimum of a half-day per visit.
 - Technician hours include travel portal to portal, so one full day visit will have proportionally more total hours on site than two half day visits.

Price \$ 4,375.00

Total Price \$ 38,610.14

Notes/Exclusions:

- Service scheduled within 2 weeks of PO.
- Excludes install and mounting hardware.

Terms:

- Net 60 Days.
- Freight included as noted.

Let me know if you have any questions on the above proposal.

Regards,

Mason Hooten PCS Pump & Process Cell: 201-916-2208

Email: mhooten@PCSPump.com



9 W SHORE DR, TOMKINS COVE, NY 10986 | WWW.WHKASSNER.COM

QUOTATION

Fabricate Only Per Attached Diagram

10 pcs	C10 X 5.28 aluminum channel with two (2) 2" holes in web and painted with black asphaltum.
20 pcs	3 X 3 X 14 washer plates with one (1) 9/16" hole

Material delivered to job site.

LOT \$3,885.00 plus tax

ERIC KASSNER, PROJECT CONSULTANT

OFFICE 845.786.5515 | **CELL** 914.447.4335

PRIVILEGED AND CONFIDENTIAL: This message and any attachments are confidential property of W.H. Kassner, Inc. The information is intended only for the use of the person to whom it was addressed. If you are not the intended addressee, you should not intercept, copy, access, or disclose this message. If you have received this message in error, please immediately notify the sender and delete the message you received. Do not forward this message without permission. The sender takes no responsibility for any unauthorized reliance on this message. Thank you. W.H. Kassner, Inc.

Subject

Shee

leet No.

1



Copy:

REQUEST FOR QUOTATION

TO: Rapid Pump & Meter Service Co., Inc.	DATE: 9/11/2020
FROM: Shivani Patel, PE	
PROJECT: NHSA PURAC System Upgrades, Phase 3 - Loan	S340952-30
KEYWORD DESCRIPTION: High-Side Impulse Taps	
DATE QUOTATION REQUIRED: 9/23/2020	
The following modification to the contract has been identified. Pursua quotation for the alteration as described in Item 1. The quotation sho subcontractor costs, including labor, materials, rentals, approved ser considered authorization to proceed with the work herein described.	ould include an itemized breakdown of contractor and
To be completed by Initiator of Request:	
Scope of Work: (include list of attachments) Furnish and install new taps on the Emergency Bypass pipes for Filter Cells #3 at newly installed filter cell differential pressure transmitters. Install the new taps on pipe run.	
2. Remove and relocate the newly installed High-Side impulse piping. Install new pi	pe and fittings as required to achieve impulse line alignment.
3. Install plug in abandoned tap.	
2. Reason(s) for Modification: Owner Unforseen The contract documents required installation of new impulse line taps in the same general location of the new filter cells, it was discovered that the location of the tap introduces air in the impulse line durin relocating the taps for Cells #3 and #4 to an area of piping that will always be filled with water, even du 3. Approval of Request:	g the filter backwash, which causes the transmitter not to work properly. We are
, рр. о о	
Owner:	Date:
Engineer: Shivani Patel, PE	Date: 9/11/2020
To be completed by Contractor:	
4. Total cost of modification (attach detailed breakdown) \$	\$1,804.81
4. Total cost of modification (attach detailed breakdown) \$	\$1,804.81
 4. Total cost of modification (attach detailed breakdown) \$ 5. Will a modification to the contract time be required? Yes 	
·	
5. Will a modification to the contract time be required? Yes	
5. Will a modification to the contract time be required?	
5. Will a modification to the contract time be required? Yes	
5. Will a modification to the contract time be required? Yes If so, trade(s) No. of personnel	⊠No (calendar days)
5. Will a modification to the contract time be required? Yes If so, trade(s) No. of personnel Duration	⊠No (calendar days)
5. Will a modification to the contract time be required? Yes If so, trade(s) No. of personnel Duration 6. Attachment identification: (list) Cost Breakdown V	⊠No (calendar days)

1.	Payroll Costs:				
	<u>Trade</u> See page 2 of Proposal		<u>Hours</u>	Rate \$	<u>Total</u> 1,479.74
				\$	-
				\$ \$	-
				SUBTOTAL: \$	1,479.74
	Material & Permanent Equipment:				
	N/A			\$	-
				SUBTOTAL: \$	-
	Subcontractor Work:	Price	Qty.		
				\$	-
				\$ \$	-
				\$	-
				SUBTOTAL: \$	-
	Supplement Costs:			Φ.	
	a. b.			\$ \$	-
	c. d.			\$ \$	-
	e.			\$	-
	f. g.			\$ \$	-
	h.			\$	-
	i. j.			\$ _\$_	-
				SUBTOTAL: \$	-
	Grand Total (Subtotal 1, Subtotal 2, Subtotal 4, Subtotal 5):			\$	1,479.74
	Contract Decrease				
	Contractor Credit			\$	-
	Net Contract Increase				
	Direct Work Sub-Total (Increase 5 + Decrease 6)			\$	1,479.74
	Contractor's Overhead (10%): Contractor's Profit (10%):			\$ \$	147.97 162.77
	Subcontractor Total (Item 3 Subtotal)			\$	-
)	Subcontractor Markup (10% of Item 10 total)			\$	-
1	Bond Premium (0.8% x Lines 8,9):			\$	14.32
2	TOTAL INCREASE:			\$	1,804.81

Labor

Laboi	<u>Men</u>	<u>Days</u>	Hrs/Day	Total Hours	<u>Rate</u>	<u>Amount</u>		<u>Total</u>
RPM Support Labor Services - RFQ-05 - Impulse Taps Cells 3/4								
Straight Time								
Supervision	1	1	4	4	Millwright	\$	89.29	\$ 357.18
Tap Installation	1 2	1	8	16	Laborer	\$	70.16	\$ 1,122.56
					TOTAL LABOR			\$ 1,479.74

Materials & Equipment

	<u>Unit</u>	<u>Qty</u>	<u>Each</u>	<u>Total</u>
NONE				\$ _

TOTAL \$ -

Trade	de Laborer		ontract Begins	5/1/2018
		S	traight	
			<u>Time</u>	
	1 Base Hourly wage	\$	34.05	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	34.05	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	2.90	
	6 Plus Fringe Benefits	\$	28.02	
	9 Subtotal	\$	64.97	
	10 Plus FICA(7.65% of 4)	\$	2.60	
	11 Plus FUTA(0.6% of 4)	\$	0.20	
	12 Plus SUI(2.0% of 4)	\$	0.68	
	13 Subtotal	\$	68.46	
	14 Plus G.L & P.D.(5.00% of 4)	\$	1.70	
	15 Total Labor Rate	\$	70.16	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens FICA FUTA	8.510% 7.650% 0.600% 2.000%
SUI	2.000%
G.L & P.D.	5.000%

Trade	e Electrician		ontract Begins	12/8/2017
		S	Striaght	
			<u>Time</u>	
	1 Base Hourly wage	\$	41.84	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	41.84	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	3.56	
	6 Plus Fringe Benefits	\$	21.97	
	9 Subtotal	\$	67.37	
	10 Plus FICA(7.65% of 4)	\$	3.20	
	11 Plus FUTA(0.6% of 4)	\$	0.25	
	12 Plus SUI(2.0% of 4)	\$	0.84	
	13 Subtotal	\$	71.66	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.09	
	15 Total Labor Rate	\$	73.75	
	0	•	-	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Trade	Millwright	С	ontract Begins	5/1/2018
		S	triaght	
			<u>Time</u>	
	1 Base Hourly wage	\$	48.80	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	48.80	
		\$	4.15	
	5 Plus Workmen's Compensation(8.51% of 4)			
	6 Plus Fringe Benefits	\$	28.90	
	9 Subtotal	\$	81.85	
	10 Plus FICA(7.65% of 4)	\$	3.73	
	11 Plus FUTA(0.6% of 4)	\$	0.29	
	12 Plus SUI(2.0% of 4)	\$	0.98	
	13 Subtotal	\$	86.85	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.44	
	15 Total Labor Rate	\$	89.29	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%




REQUEST FOR QUOTATION

	QUOTATION NO: PURAC-RFQ-06			
TO: Rapid Pump & Meter Service Co., Inc.	DATE: 9/11/2020			
FROM: Shivani Patel, PE				
PROJECT: NHSA PURAC System Upgrades, Phase 3 - Loa	an S340952-30			
KEYWORD DESCRIPTION: Work Platform Modifications				
DATE QUOTATION REQUIRED: 9/23/2020				
The following modification to the contract has been identified. Purs quotation for the alteration as described in Item 1. The quotation s subcontractor costs, including labor, materials, rentals, approved s considered authorization to proceed with the work herein describe	hould include an itemized breakdown of contractor and services, overhead, and profit. This request shall not be			
To be completed by Initiator of Request:				
• Steel platform with approximate dimensions of eighteen- foot by nine-foot 18'x9'). • Install one (1) Fixed Ladder with Safety Cage	adder extension and mods – per attached ladder modification			
2. Reason(s) for Modification: Owner Unforseen Conditions(site, weather, etc) Other The access platform was required in Cell 6 however in the design was placed in Cell 5. The design has been modified for Cell 5 which resulted in a redesign of the platform grating and ladder to accommodate the existing vertical pipe in the area.				
3. Approval of Request:				
Owner:	Date:			
Engineer: Shivani Patel, PE	Date: _ 9/11/2020			
To be completed by Contractor.				
To be completed by Contractor: 4. Total cost of modification (attach detailed breakdown) \$	\$12,260.80			
5. Will a modification to the contract time be required?	es ⊡No			
If so, trade(s)				
No. of personnel				
Duration	(calendar days)			
6. Attachment identification: (list) RFI, Cost Calcu	lations, Quotes from Vendor			
7. Quotation is in effect until: (date) 11/5/20				
8. Approval of Quotation				
Contractor RPM, Steven Marsich, P.E	Date 10/5/20			
Copy:	-			

REV 2/01 FORM 411



Request For Inform	mation/ RFI	RFI NO:	049
PROJECT: NHSA PURAC System Upgrades, Phase	3	PROJECT NO:	S340952-30
CONTRACTOR: Rapid Pump & Meter Service Co., Ir	nc. (Rapid)		
RFI Initiated By:	Steven Marsich, Rapi	d	
Regarding: Plan Sheet 16 (S-3) of 132	Spec. Section:	<u></u>	
Description:			
Steel Platform			
The Level 114 Steel Access Platform has been relocat location provides improved access to V-409E Backwas			
Please note that, as agreed, the beam anchors on the	south side are within 5	" of the expansion joint.	
As pictured below, the pre-cut aluminum grating will no cuts will be open.	longer accommodate	the pipe penetrations, and	the existing grating
Please let us know how you would like us to proceed w	vith the grating		
		Steven Marsich, P.E.	
		Prepared by	
		5/12/2020	
Response Assigned to:		Date	
		Signed	
		Date	



利為


ORIGINAL LAYOUT


NEW LAYOUT



LAYOUT AS INSTALLED







NHSA PURAC System Upgrades, Phase 3, Contract 4 PCO Cost Breakdown PCO-RFQ 06 - PLATFORM MODIFICATIONS

Des	cription: PCO Cost Breakdown					
1.	Payroll Costs: <u>Trade</u>			Центо	Bata	Total
	See page 2 of Proposal			<u>Hours</u>	Rate \$ \$	<u>Total</u> 1,479.74
					\$ \$ \$	-
					SUBTOTAL: \$	4 470 74
•	M				SUBIOTAL: \$	1,479.74
2.	Material & Permanent Equipment: See Page 3 of Proposal				\$	-
					SUBTOTAL: \$	-
3.	Subcontractor Work:	Price		Qty.		
	KASSNER	œ.	4.420	4	Φ.	4,130.00
	Provide new grating Provide new ladder SS AIS	\$ \$	4,130 5,300		\$ \$	5,300.00
					SUBTOTAL: \$	9,430.00
4.	Supplement Costs:				•	
	a. b.				\$ \$	-
	c. d.				\$ \$	-
	e. f.				\$ \$	-
	g. h.				\$ \$	-
	i.				\$	-
	j.				SUBTOTAL: \$	-
5.	Grand Total (Subtotal 1, Subtotal 2, Subtotal 4, Subtotal 5):				\$	1,479.74
	Contract Decrease					
6.	Contractor Credit				\$	-
	Net Contract Increase					
7	Direct Work Sub-Total (Increase 5 + Decrease 6)				\$	1,479.74
8	Contractor's Overhead (10%): Contractor's Profit (10%):				\$ \$	147.97 162.77
9	Subcontractor Total (Item 3 Subtotal)				\$	9,430.00
10	Subcontractor Markup (10% of Item 10 total)				\$	943.00
11	Bond Premium (0.8% x Lines 8,9):				\$	97.31
12	TOTAL INCREASE:				\$	12,260.80

LABOR/MATERIALS BREAKDOWN

Labor

	<u>Men</u>	<u>Days</u>	<u>Hrs/</u> Day	<u>Total</u> <u>Hours</u>	<u>Rate</u> Category	ļ	<u>Rate</u>	<u>Total</u>
RPM Labor Services - RFQ 06 - Platform Modifications								
Task - Modify/Weld Platform Straight Time								
Supervision	1	0.5	8	4	Millwright	\$	89.29	\$ 357.18
Welding/Modfications	2	1	8	16	Laborer	\$	70.16	\$ 1,122.56

TOTAL LABOR \$ 1,479.74

LABOR/MATERIALS BREAKDOWN

Materials & Equipment

Unit Qty Each Total

None

TOTAL \$ -

Trade Laborer	C	ontract Begins	5/1/2018
	S	traight	
		<u>Time</u>	
1 Base Hourly wage	\$	34.05	
O Dive Veresties Dev			
2 Plus Vacation Pay			
3 Plus other taxable items			
4 Taxable base	\$	34.05	
5 Plus Workmen's Compensation(8.51% of 4)	\$	2.90	
6 Plus Fringe Benefits	\$	28.02	
9 Subtotal	\$	64.97	
10 Plus FICA(7.65% of 4)	\$	2.60	
11 Plus FUTA(0.6% of 4)	\$	0.20	
12 Plus SUI(2.0% of 4)	\$	0.68	
13 Subtotal	\$	68.46	
14 Plus G.L & P.D.(5.00% of 4)	\$	1.70	
15 Total Labor Rate	\$	70.16	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Trade	Electrician	Co	ontract Begins	12/8/2017
		S	Striaght	
			<u>Time</u>	
	1 Base Hourly wage	\$	41.84	
	2 Plus Vacation Pay			
	2 Plus Vacation Pay 3 Plus other taxable items			
		Φ	44.04	
	4 Taxable base	\$	41.84	
	5 Plus Workmen's Compensation(8.51% of 4)		3.56	
	6 Plus Fringe Benefits	\$	21.97	
	9 Subtotal	\$	67.37	
	10 Plus FICA(7.65% of 4)	\$	3.20	
	11 Plus FUTA(0.6% of 4)	\$	0.25	
	12 Plus SUI(2.0% of 4)	\$	0.84	
	13 Subtotal	\$	71.66	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.09	
	15 Total Labor Rate	\$	73.75	
	0	Ψ		

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Trade	Millwright	C	ontract Begins	5/1/2018
		S	triaght	
			Time	
	1 Base Hourly wage	\$	48.80	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	48.80	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	4.15	
	6 Plus Fringe Benefits	\$	28.90	
	9 Subtotal	\$	81.85	
	10 Plus FICA(7.65% of 4)	\$	3.73	
	11 Plus FUTA(0.6% of 4)	\$	0.29	
	12 Plus SUI(2.0% of 4)	\$	0.98	
	13 Subtotal	\$	86.85	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.44	
	15 Total Labor Rate	\$	89.29	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

W.H. KASSNER, INC.

PO BOX 114 TOMKINS COVE, NY 10986 (845) 786-5515 (845) 786-2317 FAX



June 30, 2020

Proposal # WHK-NHRP-6-30-2020

Steven Marsich Rapid Pump & Meter Co. Inc. Machinery Services Corp.

North Hudson Sewerage Authority: PURAC: Rework Existing Platform

Addition to Scope per RFI 049 Furnish Only

Option 1: Replace Grating

including 3" x 3" x 3/8" steel angle framing, mill finish and railing modifications at ladder access

\$ 4,660.00 plus tax

Option 2: Reuse (2) Existing Grating Sections
Replace other sections

including 3" x 3" x 3/8" steel angle framing, mill finish and railing modifications at ladder access

\$ 4,130.00 plus tax

Notes:

- Shop drawings only.
 - No location drawings.
- No architect or engineer stamped drawings on any other items.
- Open shop fabrication.
- No installation.

No demo.

No concrete.

- Testing and inspections by others.
- WHK standard insurance. (Sample attached.)
- WHK is a certified WBE in New York State, New Jersey State and New York City.
 WHK is a certified DBE with the US Department of Transportation via the Metropolitan Transit Authority.


PAYMENT TO BE MADE AS FOLLOWS:

NET 30 DAYS . . . ABOVE PRICES NET TO YOU, PLUS STATE AND LOCAL TAXES, UNLESS OTHERWISE STATED. NAMING ADDITIONAL INSURED ON CERTIFICATES WILL INCUR SUPPLEMENTARY CHARGES.


THIS PROPOSAL MAY BE WITHDRAWN BY US IF NOT ACCEPTED WITHIN 7 DAYS. ESCALATION FEES MAY APPLY.

Ellie Kassner









W.H. KASSNER, INC.

PO BOX 114 TOMKINS COVE, NY 10986 (845) 786-5515 (845) 786-2317 FAX



June 30, 2020

Proposal # WHK-NHRP-6-30-2020

Steven Marsich Rapid Pump & Meter Co. Inc. Machinery Services Corp.

North Hudson Sewerage Authority: PURAC: Rework Existing Platform

Addition to Scope per RFI 049 Furnish Only

Option 1: Replace Grating

including 3" x 3" x 3/8" steel angle framing, mill finish and railing modifications at ladder access

\$ 4,660.00 plus tax

Option 2: Reuse (2) Existing Grating Sections
Replace other sections

including 3" x 3" x 3/8" steel angle framing, mill finish and railing modifications at ladder access

\$ 4,130.00 plus tax

Notes:

- Shop drawings only.
 - No location drawings.
- No architect or engineer stamped drawings on any other items.
- Open shop fabrication.
- No installation.

No demo.

No concrete.

- Testing and inspections by others.
- WHK standard insurance. (Sample attached.)
- WHK is a certified WBE in New York State, New Jersey State and New York City.
 WHK is a certified DBE with the US Department of Transportation via the Metropolitan Transit Authority.


PAYMENT TO BE MADE AS FOLLOWS:

NET 30 DAYS . . . ABOVE PRICES NET TO YOU, PLUS STATE AND LOCAL TAXES, UNLESS OTHERWISE STATED. NAMING ADDITIONAL INSURED ON CERTIFICATES WILL INCUR SUPPLEMENTARY CHARGES.


THIS PROPOSAL MAY BE WITHDRAWN BY US IF NOT ACCEPTED WITHIN 7 DAYS. ESCALATION FEES MAY APPLY.

Ellie Kassner









W.H. KASSNER, INC.

PO BOX 114 TOMKINS COVE, NY 10986 (845) 786-5515 (845) 786-2317 FAX



October 5, 2020

Proposal # WHK-NHPURAC-10-5-2020

Steve Marsich Rapid Pump & Meter Co. Inc. Machinery Services Corp.

Furnish Only

(1) piece ladder extension, as per S. Marsich sketch stainless steel, type 304, mill finish rungs to be stainless steel, AlGrip

Lot: \$ 5,300.00 plus tax

Notes:

- No concrete fastenings.
- No passivation.
- Shop drawings only.
 No location drawings.
 No field measurements.
- No engineering.
- Open shop fabrication.
- No installation.

No demo.

No concrete.

- Testing and inspections by others.
- WHK standard insurance.
- WHK standard AWS D1.1 Prequalified Welding Procedures only.
 WHK existing welder certifications and continuity logs only.
 Additional welding procedures or certifications will incur extra costs.
- W.H. Kassner, Inc. follows AISC practices but is not a certified AISC shop.
- WHK is a certified WBE in New York State, New Jersey State and New York City.
 WHK is a certified DBE with the US Department of Transportation via the Metropolitan Transit Authority.


PAYMENT TO BE MADE AS FOLLOWS:

NET 30 DAYS . . . ABOVE PRICES NET TO YOU, PLUS STATE AND LOCAL TAXES, UNLESS OTHERWISE STATED. NAMING ADDITIONAL INSURED ON CERTIFICATES WILL INCUR SUPPLEMENTARY CHARGES.

THIS PROPOSAL MAY BE WITHDRAWN BY US IF NOT ACCEPTED WITHIN 7 DAYS. ESCALATION FEES MAY APPLY.

Ellie Kassner







REQUEST FOR QUOTATION

		QUOTA	TION NO: PUR	AC-RFQ-07
TO: Rapid Pump & Meter Service Co.	, Inc.	DATE:	9/11/2020	
FROM: Shivani Patel, PE				
PROJECT: NHSA PURAC System	Upgrades, Phase 3 - Lo	oan S340952	-30	
KEYWORD DESCRIPTION: Air Com	pressor Circuit Breakers			
DATE QUOTATION REQUIRED: 9/2	23/2020			
The following modification to the contract quotation for the alteration as described subcontractor costs, including labor, matconsidered authorization to proceed with	in Item 1. The quotation terials, rentals, approved	should included services, ov	de an itemized bro	eakdown of contractor and
To be completed by Initiator of Reque	est:			
1. Scope of Work: (include list of atta	•			
Replace the circuit breakers of four (4) a	air compressors.			
2. Reason(s) for Modification: O	wner 🗆 Unfors	een Conditio	ons(site, weathe	r, etc) ⊠Other
_			-	· -
The circuit breakers were undersized ar the size of the circuit breaker is the low		5 WILLI LITE ALI	compressors imp	ping on startup. Increasing
3. Approval of Request:				
			Б.,	
Owner:			Date: _	
Engineer: Shivani Patel, PE			Date:	9/11/2020
To be completed by Contractor:				
4. Total cost of modification (attach de	etailed breakdown) \$	9,684.2	6	
·				
5. Will a modification to the contract ti	me be required?	Yes ⊠N	0	
	. —			
If so, t	rade(s)			
No. of	personnel			
Durati	on		(calendar day	s)
_ 			_ `	
6. Attachment identification: (list)	Cost Breakdown,	, Equipme	nt Specifica	ation
7. Quotation is in effect until: (date)	10/23/20			
8. Approval of Quotation				
			D-4-	9/23/20
Contractor	(Ma)		Date	J 23 20

NHSA PURAC System Upgrades, Phase 3, Contract 4 Cost Breakdown Replace Four (4) Compressor Circuit Breakers

Des	cription: Replace Four (4) Compressor Circuit Breakers				
1.	Payroll Costs: See page 2 of Proposal		<u>Hours</u>	Rate	<u>Total</u> 3,540.00 - -
				\$ SUBTOTAL: \$	3,540.00
2.	Material & Permanent Equipment:			SUBTUTAL. \$	3,340.00
	See Page 2 of Proposal			\$	4,400.00
•	Out and the Wester	Deine	Ot.	SUBTOTAL: \$	4,400.00
3.	Subcontractor Work: None	Price	Qty.	¢	
				\$ \$ \$	- - -
				\$ \$ \$	- - -
				SUBTOTAL: \$	-
4.	Supplement Costs: a. None.			\$	-
	b. c.			\$ \$	-
	d. e.			\$ \$	-
	f. g.			\$ \$	-
	h. i.			\$ \$	-
	j.			\$UBTOTAL: \$	<u>-</u>
5.	Grand Total (Subtotal 1, Subtotal 2, Subtotal 4, Subtotal 5):			\$	7,940.00
	Contract Decrease				
6.	Contractor Credit			\$	-
	Net Contract Increase				
7	Direct Work Sub-Total (Increase 5 + Decrease 6)			\$	7,940.00
8	Contractor's Overhead (10%): Contractor's Profit (10%):			\$ \$	794.00 873.40
9	Subcontractor Total (Item 3 Subtotal)			\$	-
10	Subcontractor Markup (5% of Item 10 total)			\$	-
11	Bond Premium (0.8% x Lines 8,9):			\$	76.86
12	TOTAL INCREASE:			\$	9,684.26

NHSA PURAC System Upgrades, Phase 3, Contract 4 Cost Breakdown Replace Four (4) Compressor Circuit Breakers

Labor		<u>Men</u>	<u>Days</u>	Hrs/Day	Total Hours	Rate	Amount	<u>Total</u>
<u>Labor</u>								
	Electrical Labor Electrician		2	8	32	Electrician (OT)	\$ 110.63	\$ 3,540.00

TOTAL LABOR \$ 3,540.00

Materials & Equipment

 Unit
 Qty
 Each
 Total

 60A 3P 277V Bolt-On Circuit Breaker
 1
 4
 \$ 1,100.00
 \$ 4,400.00

TOTAL AATERIALS \$ 4,400.00

NHSA PURAC System Upgrades, Phase 3, Contract 4 Cost Breakdown Replace Four (4) Compressor Circuit Breaker

Trade	Electrician	Со	ntract Begins	12/8/2017
		S	triaght	
		_	<u>Time</u>	
	1 Base Hourly wage	\$	41.84	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	41.84	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	3.56	
	6 Plus Fringe Benefits	\$	21.97	
	9 Subtotal	\$	67.37	
	10 Plus FICA(7.65% of 4)	\$	3.20	
	11 Plus FUTA(0.6% of 4)	\$	0.25	
	12 Plus SUI(2.0% of 4)	\$	0.84	
	13 Subtotal	\$	71.66	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.09	
	15 Total Labor Rate	\$	73.75	
	0			

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Product data sheet Characteristics

HJL36060U31X

Circuit breaker, PowerPact H, Micrologic 3.2, 60A, 3 pole, 600V, 25kA

Product availability: Non-Stock - Not normally stocked in distribution facility





Price**: 2,108.00 USD



Main

Product or component type	Circuit breaker
Range of product	PowerPact H
Trip Unit Type	Electronic, standard, Micrologic 3.2, LI
Breaking capacity code	J

Complementary

		<u>}</u>
Line Rated Current	60 A	
Number of Poles	3P	
Interrupt Rating	100 kA 240 V AC 65 kA 480 V AC 25 kA 600 V AC	,
[Ue] rated operational voltage	600 V AC	
Continuous current rating	80 %	
Mounting mode	Unit mount	2. 7
Electrical connection	Lugs load Lugs line	Ç
Wire Gauge	AWG 14AWG 3/0 aluminium/copper	.;
Maximum Height	6.4 in (162.56 mm)	
Width	4.12 in (104.65 mm)	
Depth	4.36 in (110.74 mm)	
Tightening torque	44.25 lbf.in (5 N.m) 0.000.15 in² (2.595 mm²) AWG 14AWG 3/0)	

Environment

LIMIOIIIIEII		
Product certifications	CSA	
	IEC	<u>.</u> E
	CE	r i
	CCC	<u>.</u>
	UL Listed	

Ambient air temperature for operation	104 °F (40 °C)

Ordering and shipping details

Category	01107 - H/J ELEC TRIP UNIT MOUNT BREAKER/SW
Discount Schedule	DE2
GTIN	00785901722892
Nbr. of units in pkg.	1
Package weight(Lbs)	5.8 lb(US) (2.63 kg)
Returnability	Yes
Country of origin	MX

Offer Sustainability

Sustainable offer status	Green Premium product
EU RoHS Directive	Compliant EU RoHS Declaration
Mercury free	Yes
RoHS exemption information	Yes
China RoHS Regulation	China RoHS declaration Product out of China RoHS scope. Substance declaration for your information.
Environmental Disclosure	Product Environmental Profile
Circularity Profile	End of Life Information
PVC free	Yes

Contractual warranty

Warranty	18 months



REQUEST FOR QUOTATION

	QUOTATION NO: PURAC-RFQ-02
TO: Rapid Pump & Meter Service Co., Inc.	DATE: 9/1/2020
FROM: Shivani Patel, PE	
PROJECT: NHSA PURAC System Upgrades, Phase 3 - Loa	an S340952-30
KEYWORD DESCRIPTION: Blower - Silencer	
DATE QUOTATION REQUIRED: 9/11/2020	
The following modification to the contract has been identified. Pursu quotation for the alteration as described in Item 1. The quotation should be subcontractor costs, including labor, materials, rentals, approved so considered authorization to proceed with the work herein described	should include an itemized breakdown of contractor and services, overhead, and profit. This request shall not be
To be completed by Initiator of Request:	
Scope of Work: (include list of attachments) Furnish and Install 2 Dury Universal Inlet Silaneara Madel Sp.	and DDV 10 (Inlet OC EDA AIC) for the blowers
Furnish and Install 2 Durr Universal Inlet Silencers Model Spe See attached communication with the manufacturer for mate	, ,
2. Reason(s) for Modification: Owner Unforsee	en Conditions(site, weather, etc)
To reduce noise from the blowers which was objectionable to	to the residents in the Shades Development
3. Approval of Request:	
Owner:	Date:
Engineer: Shivani Patel, PE	Date: 9/1/2020
To be completed by Contractor:	
4. Total cost of modification (attach detailed breakdown) \$	32,083.33
5. Will a modification to the contract time be required?	∕es ⊠No
If so, trade(s)	_
No. of personnel	
Duration	(calendar days)
6. Attachment identification: (list) RPM Detailed C	Cost Breakdown,Jacobs Design Dwgs
7. Quotation is in effect until: (date) 11/21/20	
8. Approval of Quotation Steven Marsich, P.E.	
Contractor RPM	
Copy:	· Van

1.	Payroll Costs:					
	Trade See page 2 of Proposal			<u>Hours</u>	<u>Rate</u> \$ \$ \$ \$ \$	<u>Total</u> 4,904.89 - - -
					SUBTOTAL: \$	4,904.89
2.	Material & Permanent Equipment: See page 2 of Proposal				\$	13,218.00
					SUBTOTAL: \$	13,218.00
3.	Subcontractor Work:	Price		Qty.		
	Craft Weld (Inspection) Alpine Painting (per specification)	\$ \$	1,500 7,500	1	\$ \$ \$	1,500.00 7,500.00 -
					SUBTOTAL: \$	9,000.00
4.	Supplement Costs: a. b. c. d. e. f. g.				\$ \$ \$ \$ \$ \$ \$ \$	- - - - - -
5.	Grand Total (Subtotal 1, Subtotal 2, Subtotal 4, Subtotal 5):				\$	18,122.89
	Contract Decrease					
6.	Contractor Credit				\$	-
	Net Contract Increase					
7	Direct Work Sub-Total (Increase 5 + Decrease 6)				\$	18,122.89
8	Contractor's Overhead (10%): Contractor's Profit (10%):				\$ \$	1,812.29 1,993.52
9	Subcontractor Total (Item 3 Subtotal)				\$	9,000.00
10	Subcontractor Markup (10% of Item 10 total)				\$	900.00
11	Bond Premium (0.8% x Lines 8,9):				\$	254.63
12	TOTAL INCREASE:				\$	32,083.33

Lal	bo	ľ
-----	----	---

Labor								
	Men Days <u>Hrs/Day</u> <u>Total Hours</u> <u>Rate</u>		<u>Rate</u>	<u>Amount</u>		<u>Total</u>		
RPM Support Labor Services - RFQ-02 - Blower Silencer Installation								
Straight Time								
Supervision	1 1	2	2	4	Millwright	\$	89.29	\$ 357.18
Beam/Silencer Installation	3	2	8	48	Laborer	\$	70.16	\$ 3,367.69
Electrical Re-Routing		1	8	16	Electrician	\$	73.75	\$ 1,180.02
					TOTAL LABOR			\$ 4,904.89

Materials & Equipment

	<u>Unit</u>	<u>Qty</u>	<u>Each</u>	<u>Total</u>
Silencers (Durr)	LS	2	\$ 4,684.00	\$ 9,368.00
Beams/Support (AIS/Kassner)	LS	1	\$ 3,850.00	\$ 3,850.00

TOTAL MATERIALS & EQUIPMENT \$ 13,218.00

Trade	Laborer	C	5/1/2018	
		S	traight	
			<u>Time</u>	
	1 Base Hourly wage	\$	34.05	
	2 Plus Vacation Pay			
	2 Plus Vacation Pay			
	3 Plus other taxable items	_		
	4 Taxable base	\$	34.05	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	2.90	
	6 Plus Fringe Benefits	\$	28.02	
	9 Subtotal	\$	64.97	
	10 Plus FICA(7.65% of 4)	\$	2.60	
	11 Plus FUTA(0.6% of 4)	\$	0.20	
	12 Plus SUI(2.0% of 4)	\$	0.68	
	13 Subtotal	\$	68.46	
		- :	1.70	
	14 Plus G.L & P.D.(5.00% of 4)	\$	-	
	15 Total Labor Rate	\$	70.16	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

.510%
.650%
.600%
.000%
.000%

Trade	Electrician	Co	ontract Begins	12/8/2017
		S	triaght	
			<u>Time</u>	
	1 Base Hourly wage	\$	41.84	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	41.84	
	5 Plus Workmen's Compensation(8.51% of 4)		3.56	
	6 Plus Fringe Benefits	\$	21.97	
	9 Subtotal	\$	67.37	
	10 Plus FICA(7.65% of 4)	\$	3.20	
	11 Plus FUTA(0.6% of 4)	\$	0.25	
	12 Plus SUI(2.0% of 4)	\$	0.84	
	13 Subtotal	\$	71.66	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.09	
	15 Total Labor Rate	\$	73.75	
	0	-		


^{*} Note: Workmens Compensation not applicable over 40 hours/week


Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%

Trade	Millwright	C	ontract Begins	5/1/2018
		S	triaght	
			Time	
	1 Base Hourly wage	\$	48.80	
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	48.80	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	4.15	
	6 Plus Fringe Benefits	\$	28.90	
	9 Subtotal	\$	81.85	
	10 Plus FICA(7.65% of 4)	\$	3.73	
	11 Plus FUTA(0.6% of 4)	\$	0.29	
	12 Plus SUI(2.0% of 4)	\$	0.98	
	13 Subtotal	\$	86.85	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.44	
	15 Total Labor Rate	\$	89.29	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

8.510%
7.650%
0.600%
2.000%
5.000%







REQUEST FOR QUOTATION

	QUOTA	HON NO: PURAC-REQ-01				
TO: Rapid Pump & Meter Service Co., Inc.	DATE:	1/17/2020				
FROM: _John V. Tobia, PE						
PROJECT: NHSA PURAC System Upgrades, Phase 3 - Loan S340952						
KEYWORD DESCRIPTION: 120V – Lockable Disconnect Switch	Plate Cove	ers – NEMA 3R				
DATE QUOTATION REQUIRED:1/31/2020						
The following modification to the contract has been identified. Pursu quotation for the alteration as described in Item 1. The quotation sh subcontractor costs, including labor, materials, rentals, approved se considered authorization to proceed with the work herein described	ould includ ervices, ove	e an itemized breakdown of contractor and				
To be completed by Initiator of Request: 1. Scope of Work: (include list of attachments)						
Furnish Model: Appleton FSK-1VS, NEMA 3R lockable switch 120VAC disconnect switches.						
Provide cost break-down. Provide total expected quantity. Provide approved SST cover plates.	ovide infoi	rmation on potential credit for not using				
2. Reason(s) for Modification: Owner Unforsee	n Conditio	ns(site, weather, etc)				
Specified cover is not capable of being locked out/tagged out.						
3. Approval of Request:						
Owner:		Date:				
Engineer: John V. Tobia, PE		Date: 1/17/2020				
To be completed by Contractor:						
	,214.7	1				
5. Will a modification to the contract time be required?	s ⊠No					
If so, trade(s)						
No. of personnel						
Duration		(calendar days)				
DDM Datailed Ducalidae	ı - Lockal	cole Switch Covers - 6/15/20				
6. Attachment identification: (list)		0,10,10				
7. Quotation is in effect until: (date) Steven Marsich P. F.						
8. Approval of Quotation Steven Marsich, P.E.						
Contractor Steven Marsich, P.E.		Date 7/15/20				
Copy:						

REV 2/01 FORM 411

FS and FD Single Gang and Tandem Cast Hub Device Box Covers Covers for Ridge Top Boxes.

	Description	Catalog Malleable Iron	Number Aluminum
ast Covers NEMA 3R Wet Locations	s — Furnished with gasket and stainless steel screws		
	Receptacle cover with spring cover. Hole Diameter — 1-7/16"	FSK-1VR	FSK-1VR-A
	For duplex flush receptacle with spring cover	FSK-1VDR	FSK-1VDR-A
	For pilot lamp flush receptacles: Red Jewel	FSK-1J-C	FSK-1-JCA
	Opal Jewel	FSK-1JOC	FSK-1JOCA
	Amber Jewel	FSK-1JAC	FSK-1JACA
	Green Jewel	FSK-1JGC	FSK-1JGCA
	For double push button switches	FSK-1PBS	—
	For external operation of tumbler switches with square handles	FSK-1VTS	FSK-1VTSA
\rightarrow	Operating type for square handle tumbler or toggle switches	FSK-1VS	FSK-1VS-A
	Rocker type for square handle tumbler or toggle flush switches	FSK-1V	FSK-1V-A
	Blank	FSK-1B-C *	FSK-1B-CA
sket - Replacement			
	Neoprene—for use with wet location covers	FS-GKR-1N	FS-GKR-1N
ast Covers Dry Locations - Furnis	hed with stainless steel screws less gasket		
	For standard 2 or 3 wire duplex receptacles	FSK-1DR-C	_
	For round flush receptacles Hole Dia. — 1-7/16"	FSK-1R-Z *	
	For square handle toggle switches	FSK-1TS-C	_
	For square handle toggle switches; Has toggle guard	FSK-1TSG-C *	FSK-1TSG-C

^{*} PVC coating available on select covers. Add suffix -PVC to catalog number.



NHSA PURAC System Upgrades, Phase 3, Contract 4 Cost Breakdown Install 152 Lockable Switch Covers

Des	cription: Install 152 Lockable Switch Covers				
1.	Payroll Costs: See page 2 of Proposal		<u>Hours</u>	Rate \$ \$ \$ \$	<u>Total</u> 1,475.02 - - -
				SUBTOTAL: \$	1,475.02
2.	Material & Permanent Equipment: See Page 3 of Proposal			\$	6,080.00
				SUBTOTAL: \$	6,080.00
3.	Subcontractor Work:	Price	Qty.		
	None			\$ \$ \$	- - -
				\$ \$ \$	- - -
				SUBTOTAL: \$	-
4.	Supplement Costs: a. None. b. c. d. e. f. g. h. i. j.			\$ \$ \$ \$ \$ \$ \$ \$ \$ \$	- - - - - - - - -
5.	Grand Total (Subtotal 1, Subtotal 2, Subtotal 4, Subtotal 5):			\$	7,555.02
	Contract Decrease				
6.	Contractor Credit			\$	-
	Net Contract Increase				
7	Direct Work Sub-Total (Increase 5 + Decrease 6)			\$	7,555.02
8	Contractor's Overhead (10%): Contractor's Profit (10%):			\$ \$	755.50 831.05
9	Subcontractor Total (Item 3 Subtotal)			\$	-
10	Subcontractor Markup (5% of Item 10 total)			\$	-
11	Bond Premium (0.8% x Lines 8,9):			\$	73.13
12	TOTAL INCREASE:			\$	9,214.71

LABOR AND MATERIAL BREAKDOWN

Labor

Men Days Hrs/Day Total Hours Rate Amount Total

Labor

Electrical Labor

Electrician 1 2.5 8 20 Electrician (ST) \$ 73.75 \$ 1,475.02

TOTAL LABOR \$ 1,475.02

LABOR AND MATERIAL BREAKDOWN

Materials & Equipment

	<u>Unit</u>	<u>Qty</u>	<u>Each</u>	<u>Total</u>
APP FSK-1VS 1G TGL COVER	1	152	\$ 40.00	\$ 6,080.00

TOTAL MATERIALS \$ 6,080.00

Trade	de Electrician		ontract Begins	12/8/2017
		S	Striaght	
			<u>Time</u>	
	1 Base Hourly wage	\$	41.84	
	0. DL . V . V . D			
	2 Plus Vacation Pay			
	3 Plus other taxable items			
	4 Taxable base	\$	41.84	
	5 Plus Workmen's Compensation(8.51% of 4)	\$	3.56	
	6 Plus Fringe Benefits	\$	21.97	
	9 Subtotal	\$	67.37	
	10 Plus FICA(7.65% of 4)	\$	3.20	
	11 Plus FUTA(0.6% of 4)	\$	0.25	
	12 Plus SUI(2.0% of 4)	\$	0.84	
	13 Subtotal	\$	71.66	
	14 Plus G.L & P.D.(5.00% of 4)	\$	2.09	
	15 Total Labor Rate	\$	73.75	
	0	Ψ	. 5 6	

^{*} Note: Workmens Compensation not applicable over 40 hours/week

Workmens	8.510%
FICA	7.650%
FUTA	0.600%
SUI	2.000%
G.L & P.D.	5.000%



A Sonepar Company

COOPER ELECTRIC 72 NORTH WASHINGTON AVENUE BERGENFIELD, NJ 07621-1700 201-385-7777 Fax 201-385-4434

don.szabo@cooper-electric.com

QUOTE TO:

RAPID PUMP & METER SERVICE CO INC

PO BOX AY

PATERSON, NJ 07509-0847

973-345-5600

Quotation

QUOTE DATE	QUOTE NUMBER
01/17/20	S039447568
P	AGE NO.
1	of 1

SHIP TO:

RAPID PUMP & METER SERVICE CO 285 STRAIGHT ST PATERSON, NJ 07509 973-345-5600

CUSTOMER NUME	BER	CUST	TOMER ORDE	R NUMBER	JOB 1	NAME	QUOTE	ED TO
214304	4	NORTH HU	JDSON	SEWER	201.874.268	87	SAM	
		PERSON			P VIA		ALLOWED	EXPIRATION DATE
								11:59pm ET
DON SZABO	<u>C</u>			CDC-06		No		02/16/20
ORDER QTY		UPC			ESCRIPTION		UNIT PRICE U	
152ea	781	38134870		FSK-1VS GL COVER			40.000 e	6080.00
TERMS & CO	ONDT	PTONS					Subtotal	6080.00

TERMS & CONDITIONS

This order is subject to Company Terms and Conditions of Sale, which provisions shall govern in the event of any conflict with any Terms or Conditions of Purchaseris proposal, purchase order or other documents. All quotes/bids for Pipe and Wire are good for the date of the bid only. No extension of the pricing of these items is authorized by any employee of the Company without express written consent in the form of an official letter or signed acknowledgement of an Officer of the Company.

Subtotal	6080.00
S&H CHGS	0.00
Sales Tax	0.00
Amount Due	6080 00



REQUEST FOR QUOTATION

		QUOTATIC	ON NO: PUR	AC-RFQ-08
TO: Rapid Pump & Meter Service Co.,	Inc.	DATE: 9	9/25/2020	
FROM: Shivani Patel, PE				
PROJECT: NHSA PURAC System	Upgrades, Phase 3 - Lo	an S340952-30)	
KEYWORD DESCRIPTION: Cell 9 and	d 10 mods			
DATE QUOTATION REQUIRED: 10/	7/2020			
The following modification to the contract quotation for the alteration as described subcontractor costs, including labor, mat considered authorization to proceed with	in Item 1. The quotation erials, rentals, approved	should include a services, overh	an itemized br	eakdown of contractor and
These modofications are for cell 9 and 10	chments) e roller mounting bracket an of the flight for (36) flights. each flight. ler mounting bracket and ch 36) x Flights to RPM's shop ts. wner	nain-link bracket.	To expedite fligh	
3. Approval of Request:			Б.,	
Owner:			Date: _	
Engineer: Shivani Patel, PE			Date:	9/25/2020
To be completed by Contractor: 4. Total cost of modification (attach de	tailed breakdown) \$	9,800		
5. Will a modification to the contract tir	·	Yes ⊠No		
If so, tr				
No. of p	personnel			
Duratio			(calendar day	s)
6. Attachment identification: (list)	Email string 4/	14/20-4/16/	/20	
7. Quotation is in effect until: (date)	11/26/20			
8. Approval of Quotation Stever	n Marsich, P.E.			
Contractor Copy:	<u> </u>		Date	10/26/20

Steven Marsich

From: Teunis Cloete <teunisc@awcsolutions.com>

Sent: Thursday, April 16, 2020 8:25 AM

To: Steven Marsich; Davidovic, Dejan/NYC; Tobia, John/NJO

Cc:Ruth Roxburgh; Wilson, Mike/BOS; Allan; Thomas J. Kazalski; Neil AllenSubject:Re: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Please go ahead

Get Outlook for iOS

From: Steven Marsich <smarsich@servicer.com>

Sent: Thursday, April 16, 2020 5:56:43 AM

To: Davidovic, Dejan/NYC <dejan.davidovic@jacobs.com>; Teunis Cloete <teunisc@awcsolutions.com>; Tobia, John/NJO

<john.tobia@jacobs.com>

Cc: Ruth Roxburgh <ruthr@awcsolutions.com>; Wilson, Mike/BOS <mike.wilson1@jacobs.com>; Allan

<allan@totalmetalworks.com>; Thomas J. Kazalski <tjkazalski@cpequip.com>; Neil Allen <neila@awcsolutions.com>

Subject: RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Dejan

As discussed, if we get the go ahead today we would like to:

- Prepare flights to bring to our office (there is still time today)
- Prepare one flight in the field to confirm that the fix will work. If AWC's representative would like to inspect the modification today to confirm that would be ideal

Please let us know when you get an update.

Thanks

SM

From: Steven Marsich

Sent: Wednesday, April 15, 2020 3:49 PM

To: Davidovic, Dejan/NYC <dejan.davidovic@jacobs.com>; Teunis Cloete <teunisc@awcsolutions.com>; Tobia, John/NJO

<john.tobia@jacobs.com>

Cc: Ruth Roxburgh <ruthr@awcsolutions.com>; Wilson, Mike/BOS <mike.wilson1@jacobs.com>; Allan

<allan@totalmetalworks.com>; Thomas J. Kazalski <tjkazalski@cpequip.com>; Neil Allen <neila@awcsolutions.com>

Subject: Re: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Dejan

We intend to do the work at our shop which would avoid prevailing wage costs for labor.

Freight and Handling: \$2,700 Labor for Modifications: \$7,100

Total Lump Sum: \$9,800

Please let us know if you need additional details

Get Outlook for iOS

From: Davidovic, Dejan/NYC <dejan.davidovic@jacobs.com>

Sent: Wednesday, April 15, 2020 3:33 PM

To: Teunis Cloete; Steven Marsich; Tobia, John/NJO

Cc: Ruth Roxburgh; Wilson, Mike/BOS; Allan; Thomas J. Kazalski; Neil Allen **Subject:** RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Teunis,

This is good news. Sounds like we are all on the same page. Rapid Pump should have a cost estimate ready for review by COB

Thanks,

Dejan Davidovic, Jacobs

Resident Engineer | North Hudson Sewerage Authority 347.528.8703 mobile 201.795.1411 office Dejan.davidovic@jacobs.com

www.jacobs.com

From: Teunis Cloete <teunisc@awcsolutions.com>

Sent: Wednesday, April 15, 2020 2:29 PM

To: Steven Marsich <<u>smarsich@servicer.com</u>>; Davidovic, Dejan/NYC <<u>Dejan.Davidovic@jacobs.com</u>>; Tobia, John/NJO <<u>John.Tobia@jacobs.com</u>>

Cc: Ruth Roxburgh <<u>ruthr@awcsolutions.com</u>>; Wilson, Mike/BOS <<u>Mike.Wilson1@jacobs.com</u>>; Allan <<u>allan@totalmetalworks.com</u>>; Thomas J. Kazalski <<u>tjkazalski@cpequip.com</u>>; Neil Allen <<u>neila@awcsolutions.com</u>> Subject: [EXTERNAL] RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Good morning folks.

I wanted to put in writing what the plan is for modification so we can do a proper estimate of the time and money it would take to rectify.

Included in original scope

1. Use a laser and shim and adjust the rails until they are parallel and straight to within 1/8" along the entire length of the cells. We would have expected this to be part of the original scope and the time spent straightening rails and getting them parallel should not be added as a charge back to AWC.

Additional scope

- 2. On the gear motor side, remove the roller mounting bracket and chain link bracket
- 3. Cut 1-1/2" off the gear motor side of the flight and extend the cut notch accordingly.
- 4. Drill new holes for the roller mounting bracket and chain link bracket as needed to adjust the overall flight length as needed to allow for a 1/8" gap between the wheel alignment shoulder and the edge of the rails on both ends (total ¼" shorter than rail edge to edge distance).

- 5. On the opposite sides to the gear motor, move the sprocket location on both drive shaft and idler shaft to accommodate the existing location for the chain link bracket. We anticipate this will equate to a 5/8" move of both sprockets towards the center of the cell.
- 6. Verify overall roller shoulder to shoulder length requirements and reassemble the gear motor side roller mounting bracket and chain link bracket to match.
- 7. Redline drawing to reflect all changes made to the supplied equipment to make it work / fit.

Tom mentioned that RP believes they can save time and money by moving all the flights to their shop and applying the modifications there. AWC would like to use every opportunity to minimize the cost and we would be fine with the work happening at RP shop provided the cost savings considers all costs including lifting, transport, tooling etc.

Please review and let me know if you agree with the scope. Then RP can estimate the cost for approval prior to doing the work.

Thank you.

Teunis Cloete, P.Eng., Senior Engineer C 403 970 4060 | www.awcsolutions.com

From: Steven Marsich <smarsich@servicer.com>

Sent: April 15, 2020 8:55 AM

To: Davidovic, Dejan/NYC < dejan.davidovic@jacobs.com; Teunis Cloete < teunisc@awcsolutions.com; Tobia, John/NJO < john.tobia@jacobs.com>; Tobia, John/NJO

Cc: Ruth Roxburgh <<u>ruthr@awcsolutions.com</u>>; Wilson, Mike/BOS <<u>mike.wilson1@jacobs.com</u>>; Allan

<allan@totalmetalworks.com>; Thomas J. Kazalski <ti>tjkazalski@cpequip.com></ti>

Subject: Re: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Dejan, Teunis

Wet think we need an additional six holes (or slots) for the flight bracket plus one more for skirtboard backing plate

SM

Get Outlook for iOS

From: Davidovic, Dejan/NYC <dejan.davidovic@jacobs.com>

Sent: Wednesday, April 15, 2020 11:12 AM

To: Teunis Cloete; Steven Marsich; Tobia, John/NJO

Cc: Ruth Roxburgh; Wilson, Mike/BOS; Allan; Thomas J. Kazalski

Subject: RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Teunis,

See below in red.

Dejan Davidovic, Jacobs

Resident Engineer | North Hudson Sewerage Authority 347.528.8703 mobile 201.795.1411 office Dejan.davidovic@jacobs.com

www.jacobs.com

From: Teunis Cloete <teunisc@awcsolutions.com>

Sent: Wednesday, April 15, 2020 11:07 AM

To: Davidovic, Dejan/NYC < <u>Dejan.Davidovic@jacobs.com</u>>; Steven Marsich < <u>smarsich@servicer.com</u>>; Tobia, John/NJO < <u>John.Tobia@jacobs.com</u>>

Cc: Ruth Roxburgh <ruthr@awcsolutions.com>; Wilson, Mike/BOS <Mike.Wilson1@jacobs.com>; Allan

<allan@totalmetalworks.com>; Thomas J. Kazalski <tjkazalski@cpequip.com>

Subject: [EXTERNAL] RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Hi Dejan

I don't want to churn on this too much.

Please provide a verification of the following:

Are the dimensions provided on the RFI correct?

2. Are the dimensions reflective of the narrowest point of the cells, or do the cells narrow along the length? If so, by how much?

Narrowest point

3. Can we get an estimate of the cost for cutting one end of each flight (by roughly 2") and drilling 4 new holes? The end trucks are slotted, so the flight just requires holes, not slots.

Yes. Do you need cost estimate for both Cells 9 and 10 or just cell 10?

Thank you for your patience.

Teunis Cloete, P.Eng., Senior Engineer C 403 970 4060 | www.awcsolutions.com

From: Davidovic, Dejan/NYC < Dejan. Davidovic@jacobs.com >

Sent: April 15, 2020 6:33 AM

To: Teunis Cloete < teunisc@awcsolutions.com; Steven Marsich < smarsich@servicer.com; Tobia, John/NJO < John.Tobia@jacobs.com; Tobia, John/NJO < John.Tobia@jacobs.com; Tobia, John/NJO < smarsich@servicer.com; Tobia, John/NJO <a href="mailto:smarsich@servicer.c

Cc: Ruth Roxburgh <<u>ruthr@awcsolutions.com</u>>; Wilson, Mike/BOS <<u>Mike.Wilson1@jacobs.com</u>>; Allan <allan@totalmetalworks.com>

Subject: RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Teunis,

Please see attached e-mail. Does the attached RFI 033 wall to wall dimension match your Cell 9 & 10 field measurements taken last year while on site redesigning Cells 3 and 4?

Also, RPM checked cells 3 and 4 flights, they appear to be a different design, and length when compared with Cells 9 and 10.

Thanks,

Dejan Davidovic, Jacobs

Resident Engineer | North Hudson Sewerage Authority 347.528.8703 mobile

Dejan.davidovic@jacobs.com

www.jacobs.com

From: Teunis Cloete <teunisc@awcsolutions.com>

Sent: Wednesday, April 15, 2020 9:25 AM

To: Davidovic, Dejan/NYC NYC Cejan.Davidovic@jacobs.com; Steven Marsich servicer.com; Tobia, John/NJO

<John.Tobia@jacobs.com>

Cc: Ruth Roxburgh <ruthr@awcsolutions.com>; Wilson, Mike/BOS < Mike.Wilson1@jacobs.com>; Allan

<allan@totalmetalworks.com>

Subject: [EXTERNAL] Re: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Please confirm the wall to wall dimension. It seems strange given the table you provided yesterday.

Get Outlook for iOS

From: Davidovic, Dejan/NYC < Dejan. Davidovic@jacobs.com >

Sent: Wednesday, April 15, 2020 7:22:08 AM

To: Teunis Cloete <teunisc@awcsolutions.com>; Steven Marsich <smarsich@servicer.com>; Tobia, John/NJO

<John.Tobia@jacobs.com>

Cc: Ruth Roxburgh < ruthr@awcsolutions.com >; Wilson, Mike/BOS < Mike.Wilson1@jacobs.com >; Allan

<allan@totalmetalworks.com>

Subject: RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Teunis.

Agreed, it appears form attached pictures that all (18) flights for Cell 10 will have to be cut back/shortened. See attached pictures of the flight in cell 10.

Please, note that all shims behind the rail support brackets will be re-installed once the flight modifications are implemented. So, flights don't have conflict with the take-ups on the North end of cell.

Not sure if it helps, but Steve Kelly of RPM is available for a call if you require.

Thanks,

Dejan Davidovic, Jacobs

Resident Engineer | North Hudson Sewerage Authority 347.528.8703 mobile 201.795.1411 office Dejan.davidovic@jacobs.com

www.jacobs.com

----Original Message-----

From: Teunis Cloete <teunisc@awcsolutions.com>

Sent: Tuesday, April 14, 2020 5:35 PM

To: Davidovic, Dejan/NYC < <u>Dejan.Davidovic@jacobs.com</u> >; Steven Marsich < <u>smarsich@servicer.com</u> >; Tobia, John/NJO

<<u>John.Tobia@jacobs.com</u>>

Cc: Ruth Roxburgh <<u>ruthr@awcsolutions.com</u>>; Wilson, Mike/BOS <<u>Mike.Wilson1@jacobs.com</u>>; Allan <allan@totalmetalworks.com>

Subject: [EXTERNAL] RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Hi Dejan.

From the information Steve provided, the flights will not fit. We need to get a good understanding of our options which is why I looped in Allan to help us determine a path forward.

Teunis Cloete, P.Eng., Senior Engineer P 604 936 4217 ext 521

https://urldefense.com/v3/ http://www.awcsolutions.com ;!!B5cixuoO7ltTeg!XIP3sWClETFLzV0O0eFKlwvPcCHfcN25 EEKzPmfkeigYw8g59USKflI7Z0wYj-Rmtjsacw\$

----Original Message----

From: Davidovic, Dejan/NYC < Dejan. Davidovic@jacobs.com >

Sent: April 14, 2020 2:19 PM

To: Steven Marsich <<u>smarsich@servicer.com</u>>; Teunis Cloete <<u>teunisc@awcsolutions.com</u>>; Tobia, John/NJO <<u>John.Tobia@jacobs.com</u>>

Cc: Ruth Roxburgh < ruthr@awcsolutions.com; Wilson, Mike/BOS < Mike.Wilson1@jacobs.com>

Subject: RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

- Steve,

It appears we have very similar measurements. Thank you for the confirmation/update. Lets install a few flights tomorrow and see what the issues are.

- Teunis,

Can you confirm if below measurements of flights are acceptable and as per design?

Thanks,

Dejan Davidovic, Jacobs

Resident Engineer | North Hudson Sewerage Authority 347.528.8703 mobile 201.795.1411 office Dejan.davidovic@jacobs.com

http://www.jacobs.com

----Original Message-----

From: Steven Marsich < smarsich@servicer.com >

Sent: Tuesday, April 14, 2020 5:08 PM

To: Davidovic, Dejan/NYC < Dejan.Davidovic@jacobs.com; Teunis Cloete < teunisc@awcsolutions.com; Tobia, John/NJO

<John.Tobia@jacobs.com>

Cc: Ruth Roxburgh <ruthr@awcsolutions.com>; Wilson, Mike/BOS <Mike.Wilson1@jacobs.com>

Subject: [EXTERNAL] RE: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Dejan

The critical dimension is how the flight fits on the rails. There is a larger wheel on the flight that butts up against the inside of the rails. I attached a picture of Cell 3 for reference.

The critical dimension on the rail is the distance between the outside of the larger wheels which is 256 5/8"

The critical dimension in cell is the distance between the inside of the rails = 256 1/8"

Note that these measurements were taken with the rail fully collapsed (it is adjustable in length), and with all shims removed from the rails. If we put the flight in the cell the large wheel will ride on top of the rail as it is 1/2" to long even with all possible adjustments made.

Let me know if this is clear.

Thanks

SM

-----Original Message-----

From: Davidovic, Dejan/NYC [mailto:Dejan.Davidovic@jacobs.com]

Sent: Tuesday, April 14, 2020 4:40 PM

To: Steven Marsich < smarsich@servicer.com; Teunis Cloete < teunisc@awcsolutions.com; Tobia, John/NJO

<<u>John.Tobia@jacobs.com</u>>

Cc: Ruth Roxburgh <<u>ruthr@awcsolutions.com</u>>; Wilson, Mike/BOS <<u>Mike.Wilson1@jacobs.com</u>>

Subject: NHSA PURAC P3: - Cell 9 and 10: - Skimmer: - Flights Length

Steve,

Just taken some measurements of new flights - Cell 9 and 10. It appears they are good to go. Cell 9 and 10 flights are not exactly the same length. Approximately at 21'-2" long for each cell. Which is less than approximate 22-ft cell width opening. (In addition it allows for wiper clearance.) See attached pictures.

Per attached pictures and RFI 033 Response from back in June of 2019, the new flights should be good to go. (My only concern is the South side of the Cell where it is narrower than the North side of the cell.)

Let's install a few flights tomorrow if at all possible.

Can you share your measurements of skimmer flight lengths taken earlier?

Thanks,

Dejan Davidovic, Jacobs

Resident Engineer | North Hudson Sewerage Authority 347.528.8703 mobile 201.795.1411 office Dejan.davidovic@jacobs.com

http://www.jacobs.com

----Original Message-----

From: Steven Marsich < smarsich@servicer.com >

Sent: Tuesday, April 14, 2020 2:42 PM

To: Teunis Cloete <teunisc@awcsolutions.com>; Davidovic, Dejan/NYC <Dejan.Davidovic@jacobs.com>; Tobia, John/NJO

<John.Tobia@jacobs.com>

Cc: Ruth Roxburgh <ruthr@awcsolutions.com>

Subject: [EXTERNAL] RE: PRO#4642 AWC North Hudson shipment info

Teunis

Can you confirm all the measurements you are using for the cells? We would like to confirm again in the field just to make sure.

Thanks

SM

----Original Message----

From: Teunis Cloete [mailto:teunisc@awcsolutions.com]

Sent: Tuesday, April 14, 2020 10:27 AM

To: Davidovic, Dejan/NYC < Dejan.Davidovic@jacobs.com >; Tobia, John/NJO < John.Tobia@jacobs.com >

Cc: Ruth Roxburgh < ruthr@awcsolutions.com; Steven Marsich smarsich@servicer.com>

Subject: RE: PRO#4642 AWC North Hudson shipment info

Hi Folks

I received a request from our flight fabricator asking which cells are next.

They are planning to ship the next three cells before the end of the month, but want to set the width based on measurements they took while at site.

Please let me know ASAP. This should reduce work at site.

Teunis Cloete, P.Eng., Senior Engineer P 604 936 4217 ext 521

https://urldefense.com/v3/ http://www.awcsolutions.com ;!!B5cixuoO7ltTeg!Sg-

jRNr8g1vyyDlyUOz8gDtRo5twGfnAxaQ1sDn8mebwXNtDaMyewXPmfAUK1ao0w1Db7w\$ -----Original Message-----

From: Davidovic, Dejan/NYC < Dejan. Davidovic@jacobs.com >

Sent: April 14, 2020 7:14 AM

To: Teunis Cloete < teunisc@awcsolutions.com; Tobia, John/NJO < John.Tobia@jacobs.com> Cc: Ruth Roxburgh < teunisc@awcsolutions.com; Steven Marsich < smarsich@servicer.com>

Subject: RE: PRO#4642 AWC North Hudson shipment info

Thank you Teunis.

Any updates on the delivery date of remaining (3) underdrain LP-Block pallets?

Dejan Davidovic,

Jacobs

Resident Engineer | North Hudson Sewerage Authority 347.528.8703 mobile 201.795.1411 office Dejan.davidovic@jacobs.com

http://www.jacobs.com

----Original Message----

From: Teunis Cloete < teunisc@awcsolutions.com>

Sent: Tuesday, April 14, 2020 10:09 AM

To: Davidovic, Dejan/NYC < <u>Dejan.Davidovic@jacobs.com</u> >; Tobia, John/NJO < <u>John.Tobia@jacobs.com</u> > Cc: Ruth Roxburgh < <u>ruthr@awcsolutions.com</u> >; Steven Marsich < <u>smarsich@servicer.com</u> > Subject: [EXTERNAL] FW: PRO#4642 AWC North Hudson shipment info
FYI. The remaining drop pipes are scheduled to arrive tomorrow morning. The packing list was sent before, but essentially there are 4 spool pieces per cell for 6 cells.
NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.
NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.
NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.
NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.
NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.
NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.

NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.